

MAP NO. _____

ELEV. 2030DF, 2033KB

STATE Kans COUNTY Clark SEC. 35 Twp 32S Rge 23W

OPERATOR McClellan Drlg. Co. LOC. C NW SE


WELL NO. 2 FARM NAME Abell FT. FROM _____ LINE _____

POOL Ashland FT. FROM _____ LINE _____

FR. 3-26-62 SPUD 3-11-62 COMP. 7-31-62

CONT./GEOL. Co. tools

NAME PRODUCING INTERVAL	COMPLETION RECORD		TREATMENT RECORD
	FROM -- TO	PERF. W/HOLES	
a. <u>Lans Zn # 1</u>	<u>4467</u>	<u>4-Way Jet</u>	<u>Nat</u>
b. <u>Lans Zn # 2</u>	<u>4692</u>	<u>4-Way Jet</u>	<u>1250 A</u>



d. State Por: Flow

d. I. P. OIL/DIST. 42 BO WTR. Tr Gas No Ga M.C.F.P.D. _____ CHK. _____ HRS. 24

b. " " (Lans Comingled Oil)" " " "

c. " Dual " " " " " "

d. 4467 - F/144 BOPD
4692 - F/108 BOPD D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. 39.6 deg PBT _____ TD 4760

SIZE	DEPTH	CASING - CEMENT RECORD		DEPTH	W/SAX.
		W/SAX.	SIZE		
<u>8 5/8"</u>	<u>527</u>	<u>350</u>	<u>1 1/2" tbg</u>	<u>4696</u>	
<u>5 1/2"</u>	<u>4759</u>	<u>150</u>	<u>1 1/2" tbg</u>	<u>4468</u>	

OPERATOR McClelland Drlg Co WELL NO. 2 Abell ELEV. 2033 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
-------------	-------	---------	------------	-------	---------

(No sample tops)			KB Tops & Datums		
RTD (Lans)	4760	-2727	Hb	4205	-2172
			Tor	4237	-2204
			Lans	4406 T*	-2373
			Lans Zn # 1	4466 T*	-2433
			Lans Zn # 2	4682 T*	-2649
			LTD	N.A.	

DST # 1 (Lans) 4461-72, op 1 hr, GTS/6", R 850' GO & 270' MCO & 170' SW, IBHP 1655#/NT, IFP 150#, FFP 415#, FBHP 1625#/NT.

DST # 2 (Lans) 4663-98, op 90", GTS/2", Ga 369 MCFGPD/5", Ga 560 MCFGPD/15" and stab @ 60", Ga 590 MCFGPD/60" & stab, R 900' MCO, IBHP 880#/30", IFP 125#, FFP 205#, FBHP 785#/30".

DST # 3 (Lans) 4710-32, op 90", fair blo/90", R 120' sli oil spk mud & 90' thin wtry mud, IBHP 1580#/30", IFP 0#, FFP 265#, FBHP 565#/30".

RTD 4760, Log. 5 1/2" @ 4759 w/150 sx. GRN Log. 4-Way Jet 4692 (Lans) No tst, Nat. 500 A S/ld. S 4 1/2 BOPH/24 hrs + gas Ga 250 MCFGPD w/ sho form wtr, PB 4500. 4-Way Jet 4467 (Lans) GTS immed, no ga. Flo 5 BO/1 hr. Swb 26 BNO/7 hrs. Gas TSTM w/sho form wtr.

7-296W

SHEET NO. 2

MAP NO. _____

STATE Kans COUNTY Clark SEC. 35 Twp 32S Rge 23W

OPERATOR McClellan Drlg. Co. LOC. C NW SE

WELL NO. 2 FARM NAME Abell

Re-acid, 750 A @ 4692. S/ld, 1½" tbg w/pkr @ 4696, 1½" tbg to 4468. State Pot: (24 hr flo) Flo 42 BOPD & tr wtr. Gr 39.6 deg. Lans 4467-4692. Note: This is not dual completion. This test is for both Lans Zones which are produced alternately and all oil is comingled.
7-24-62.

COMPLETED

OPERATOR

WELL NO.