

15-189-22682

30-32s-37w

Jed


TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

EOG Resources

Glenda 30-#1

3817 NW EXPWY STE 500
Oklahoma City OK, 73112

30/32/37

Job Ticket: 34031

DST#: 1

ATTN: Preston Heiskell

Test Start: 2009.03.30 @ 01:25:02

GENERAL INFORMATION:

Formation: **Lower Morrow**

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 06:29:32

Time Test Ended: 14:09:32

Test Type: Conventional Bottom Hole

Tester: Mike Slomp

Unit No: 28

Interval: **6002.00 ft (KB) To 6038.00 ft (KB) (TVD)**

Reference Elevations: 3109.00 ft (KB)

Total Depth: 6038.00 ft (KB) (TVD)

3097.00 ft (CF)

Hole Diameter: 7.78 inches Hole Condition: Fair

KB to GR/CF: 12.00 ft

Serial #: 6752

Inside

Press@RunDepth: 70.88 psig @ 6004.00 ft (KB)

Capacity: 7000.00 psig

Start Date: 2009.03.30

End Date: 2009.03.30

Last Calib.: 2009.03.30

Start Time: 01:25:03

End Time: 14:09:32

Time On Btm: 2009.03.30 @ 06:28:11

Time Off Btm: 2009.03.30 @ 11:02:42

CONFIDENTIAL

TEST COMMENT: IF- Strong blow, BOB in 6 min

IS- No blow back


FF- Strong blow, BOB in 1 min

FSI- No blow back

MAY 27 2009

KCC

Pressure vs. Time



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	3134.93	130.23	Initial Hydro-static
2	50.03	130.09	Open To Flow (1)
33	48.55	135.14	Shut-In(1)
92	1101.11	136.82	End Shut-In(1)
93	51.33	137.69	Open To Flow (2)
151	70.88	139.48	Shut-In(2)
271	1467.19	141.08	End Shut-In(2)
275	2829.15	141.90	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
100.00	100% mud	0.49

Gas Rates

Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
----------------	-----------------	------------------

RECEIVED

MAY 28 2009

KCC WICHITA

Pressure vs. Time

