


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

NORTHERN NATURAL GAS CO.
Lightcap No. 1.

SEC. 36 T. 32 R. 37W
NEc NW

Total Depth. 2845'
Comm. 7-25-41 Comp. 8-14-41
Shot or Treated.
Contractor.
Issued. 11-1-41

County. Stevens



CASING:

10" 613'
7" 2655'

Elevation.

Production. 33,411,000 Gas

Figures Indicate Bottom of Formations.

sand & gravel	0-510
gyp	522
sand	565
red bed	644
red bed & gyp	800
sand & red bed	983
red bed & gyp	1244
sand & gyp	1537
red bed & gyp	1762
brkn lime & gyp	1784
shale & gyp	1785
shale & gyp	2449
anhydrite & gyp	2490
shale	2505
shale & gyp	2530
anhydrite & shale	2597
lime	2608
shale	2618
lime	2700
shale blue	2708
lime	2739
shale	2758
lime	2845
Total Depth.	

Open flow before acid 5,500,000 Gas
Open flow after acid 33,411,000 Gas

1st gas 2670' - 300,000
increase - 2710-2715 - 1,300,000
increase - 2715-2735 - 5,000,000
increase - 2758-2765
2805' - 5,500,000
2845' T.D. - 5,500,000