

1-101W

Map No. 82

REPL # 1

ER MESA PETROLEUM CO
BOX 2009, AMARILLO, TEXAS

WELL #2-5 ROBINSON


CONTR FWA DRLG CO

FIELD PANOMA FIELD (C GR)

I.P. CO IPF 5,450 MCFGPD C GR 2877-2980

API # 15-189-20082

PTD 2986'



S-T-R 5-32S-37W

SPOT APP C W¹/₂

CO STEVENS, KS

ELEV 3146 KB

3135 GR

2600' FNL &

1440' FWL

SPUD 12-20-69 8 5/8" @ 612/500 COMPANY GEOLOGIST

NO CORES NO DSTS

RTD 3020 NO LOG 5 1/2" @ 3016 W/300 ON 12-24-69

MICT CO LOG PERF (C GR) 8/2877-79, 8/2883-85,
20/2889-94, 16/2900-04, 12/2915-18, 8/2925-27, 4-2935-36,
8/2939-41, 52/2947-60, 48/2968-80, 5000(15%) ACID + 225
BALL SEALERS, MP 1700#, TP 825#, AIR 30 BPM, FRAC W/3000
BW X 100,000# SD AIR 30 BPM, FRAC W/3000 BW X 100,000# SD
AIR 154 BPM, SWBD IN - UNLOADED FRAC FLUID BLOW TO DRY/24
HRS, KILLED WELL - RAN 2968' OF 1 1/2" TBG, CO IPF 5,450
MCFGPD C GR 2877-2980 COMPLETED 1-19-70

REPLACES COMP ISSUED 1-22-70REPLACED TO ADD ALL INFO

KB LOG TOPS

HERR 2518 + 628

C GR 2868 + 278

LTD NA

RTD 3020 + 126

TD IN C GR FORM

REPL COMP ISSUED 3-5-70