


640 Acres
N

API # 15-189-20, 161



Locate well correctly

Lease Name: Dold "A" Well No. 1
 Well Located: 1250' FN&EL
Stevens SEC 33 TWP 32S RGE 38W
 Operator: Anadarko Production Company
 Address: Box 351 Liberal, Kansas 67901
 Elevation: Ground 3180.3 D.F. K.B.
 Type Well: (Oil, gas, dry hole) Gas

Drilling Commenced: 1/2 19 73 Drilling Completed: 1/13 19 73
 Well Completed: 1/29 19 73 Total Depth
 Initial Production: Gas gauged 1023 MCF/D thru tubing.

Casing Record

Size: 8 5/8 Set at 504 Size: Set at
 Size: 5 1/2 Set at 2984 Size: Set at

Liner Record

Size: Set from To

Cementing

<u>Casing Size</u>	<u>Sacks</u>	<u>Type Cement and Additives</u>
<u>8 5/8</u>	<u>550</u>	<u>Common 3% CC.</u>
<u>5 1/2</u>	<u>500</u>	<u>Lite Wate W/12 1/2# Gilsonite/sx.</u>
<u>5 1/2</u>	<u>150</u>	<u>Salt Sat Pozmix W/.5% CFR-2.</u>

Perforations

<u>Formation</u>	<u>Perforated Interval and Number Shots</u>
<u>Council Grove</u>	<u>2839-2947 2 SPF (78 Shots.)</u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>
<u> </u>	<u> </u>

Electric Log Run (Show type log and depths covered)

GRN 1500-2985
GRCL 2500-2957

(Fill in formation and related information on reverse side)

FORMATION, TESTING AND COMPLETION RECORD

Show Drill Stem Tests,
Well Stimulation and
Production Tests

Formation	Top	Bottom	
Surface Sand & Clay	0	460	Acidized 2943-47 W/500 Gals. 15%.
Red Bed	460	679	Acidized 2920-28 W/1000 Gals. 15%.
Sand & Shale	679	1690	Fraced W/120,000 Gals. Water + 100,000# Riversand.
Shale & Shells	1690	1906	CWHOF 2189 MCF/D (Check Test).
Shale & Lime	1906	2035	
Lime & Shale	2035	2985	
TOTAL DEPTH	2985		