

6-128W

MAP NO. 83

SEC 3-32S-38W

STATE Kansas COUNTY Stevens

LOC C NE SW

OPER Anadarko Production Co., Liberal, Kansas

FT/FR LINE

WELL #2 FARM Leonard "B"

FT/FR LINE

WELL HUGOTON

ELEV. 3172 GR 3177 DF 3179 KB

NT. Earl F. Wakefield Tools

GEOLOGICAL Gordon Kiddoo

CU. INT. 3130' test

F.R. 5/1/64 SPUD 4/30/64 COMP. 6/9/64

TD 3154 FM. CG PBT. 2934

Completion Record	PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
	CG	2892 - 2922		46	Frac
	I.P. Ga 3,545,000 Cfgpd/90 min. BD				

Casing Record 8-5/8" @ 610 w/400 sx.

4 1/2" @ 3147 w/250 sx.

Data Inc.

KB Log Tops:

B/Cimm	1760 +1419	U/FR	2643 + 536	RTD	3154 + 25
Kri	2498 + 681	CG	2810 + 369		
Winf	2572 + 607	LTD	3150 + 29		

Lost circ @ 2357; lost circ @ 2679, RTD 3154, Log, 4 1/2" @ 3147
/250 sx., CO 3112, Pf 40/2970-80 (CG) 500A, $\text{B } 4$ GWPH (Filt)

10 hrs, $\text{B } 2$ GWPH, NT, Clor 80,000 PPM, 12/2956-59, 8/2940-42,
16/2918-22, 40/2892-2902 (CG) 1694 GA, $\text{S } 128$ GW +
62,000 Cfg/9 hrs from 2892-2902, Plug 2934, Frac 60,000 GW x
90,000# sd x 15,000# RS (2892-2922) 4 hr. BD, Ga 3,600,000 Cfgpd
w/5 B 1d, PH/13 hrs, BD, Ga 2,800,000 Cfgpd w/mist of wtr, 1 1/2 hr.
BD, Ga 3,545,000 Cfgpd + mist wtr, SICP 300#, CG 2892-2922,

COMPLETE (6/1/64)

CSO EL Log

Win 2572 + 600

C Gro 2832 + 340 $\&$ 3.5A