


1-70W Map No. K83
OPER ANADARKO PROD. CO. - Liberal, Ks.
Well is Twin to #1 (Replacement)
WELL #2 HOWELL "B"
Moran Brothers
FIELD Panoma Gas Area (C Gr)
I.P. Ga 3,972,000 Cfgpd, C Gr 2836-2984



S-T-R 20-32S-38W
SPOT App C NW NE
CO STEVENS (Ks)
ELEV 3198 GR

Note: Twin to #1 (Replacement)

(GR Log)
C Gr 2816 $\neq$ 382
LTD 3030 $\neq$ 168
RTD 3030 $\neq$ 168

No DST's, RTD 3030, Log, 5 $\frac{1}{2}$ " @3030 w/200 sx.

12/2978-84 (C Gr) No sho nat, 500A, Ga 340,000 CFGPD $\neq$
10 GW, 4/2964-66, 4/2949-51, 12/2926-32, 20/2901-11,
2/2886-87, 2/2863-64, 2/2852-53, 2/2845-46, 2/2836-27
(C Gr) Ga 340,000 CFGPD $\neq$ 20 GW/1 hr, 3000A, Ga 340,
000 CFGPD $\neq$ 40 GWPH/7 hrs, Frac 95,000 GW x 75,000#
sd, flow ld, Ga 3,972,000 CFGPD, SICP 268#/114 hrs,
CGr 2836-2984 - COMPLETED on 1-4-66

win 2636 + 562
CGr 2840 + 358

Data Inc

MISC DATA

GEOL _____ ELEV 3208 DF SPUD DATE 12-6-65
FTG 2080' FEL x 660' FNL 3211 KB DRLG COMP _____
SUPPT _____ FR by DATA 11-17-65
CSG 8" @594 w/400 sx. 5" @3030 w/200 sx. COMP by " 1-6-66

L-S 3203 EDF
3198 GL