


90101

1-254W MAP NO. 83 SEC. 16-32S-38W
 STATE Kans. COUNTY Stevens LOC. C NW SE
 OPER Gas Inc. & Walter Kuhn, Wichita, Kansas FT/FR _____ LINE _____
 WELL #A-2 FARM McClure 253188 FT/FR _____ LINE _____
 TOOL Geol. WC in Hugoton Area * ELEV. _____ GR. 3187 DF. 3190 KB _____

INT. D. & M. Drlg. Tools GEOL. Mr. Little
 INT. Anadarko Prod. Co. (FO) Mobil Oil Co. (Support)
 F.R. 11/5/63 SPUD. 11/8/63 COMP. 1/21/64
 TD. 6351 FM. St L PBDT. 3018 (?)



Completion Record	PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT
		CG	2912-2985	124	1000A & Frac
Casing Record	I.P. <u>72-20; 8,870,000 Cfgpd (SIP 298#)</u>				
	* <u>6 miles East of Kinsler Field (Miss-Marm & Marm Gas)</u>				
	<u>13" @ 575 w/575 sx. 8-5/8" @ 3045 w/650 sx. 5 1/2" @ 6084 w/100 sx. 6200' Oil Test</u>				

KB Spl Tops:	KB Log Tops & Datums:
Wab 3345-3431	CG 2831 + 359 Cher 5050 -1860
Lans 4131	Wab 3264 - 74 Mrw 5582 -2392
RTD 6330	Top 3535 - 345 Mrw sd 5978 -2788
	Tor 4082 - 892 B/sd 6006 -2816
	Lans 4154 - 964 Ches 6051 -2861
	Marm 4878 -1688 St G 6144 -2954

DST #1 (CG) 2918-36, Op 20", failed St L 6276 -3086
 DST #2 (CG) 2920-3071, Op 30", GTS/3", LTD 6351 -3161
 TSTM, R 20' GCM + 267' HGCM + 88' GCW,
 ISIP 399#/30", IFP 88#, FFP 125#, FSIP 399#/30"
 DST #3 (Wab) 3345-3431, Op 36", R 120' M, ISIP 728#/30", IFP 36 1/2#
 FFP 73#, FSIP 674#/30"
 DST #4 (Marm) 4868-4906, Op 55', R 295' MSW, ISIP 1387#/30",
 IFP 66#, FFP 175#, FSIP 1200#/30"
 DST #5 (L Mrw) 5967-6005, Op 5", SI/30", Op 45", SI/30", R 25' OCM
 ISIP 591#/30", IFP 22#, FFP 44#, FSIP 219#/30"
 RTD 6330 (Miss), Log,
 WLT #1 (Mrw) 5988-90 1/2, R 750 cc filt wtr, ISIP 50#/17", SP 0#,
 FSIP 50#/40"
 5 1/2" @ 6084 w/100 sx, WOCT, Vert frac, notch @ 5988-5994 (L/Mrw)
 G, Nat, Mud broke in, Sq 5988-94 w/100, CO, Pf 12/5991-94 (L/Mrw)
 250A + Frac 10,000 GO x 10,000# sd, \$ pt ld w/GSO, \$ 10 BFPH (90%
 SW)/NT, PB 3018?, 68/2912-30, 40/2940-50, 16/2981-85 (CG) 1000A,
 Frac 84,000 GW x 100,000# sd, Ga 5,000,000 cfgpd + ld, Ga 7,500,000
 cfgpd (wet) 72/20 Ga 8,870,000 cfgpd, SIP 298#, CG 2912-2985,

COMPLETE (1/11/64)

LIBERAL ELECTRIC LOG TOPS

3190 KB

Winfield 2600 (+590)

Council Grove 2858 (+332) ϕ 8,800 MCF

Heebner 4062 (-872)

Toronto 4086 (-896)

Lansing 4180 (-990)

Marmaton 4878 (-1688) Tst XW

Morrow 5608 (-2418)

"S-3" 5978 (-2788) 22/28; ϕ 10 BFLPH (90% XW)

Chester 6006 (-2816)

Ste. Gen 6186 (-2996)

St. Louis 6276 (-3086)

TD 6330

St. Louis