

R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22328-00-00
Spot: SENWNW Sec/Twnshp/Rge: 5-32S-38W
4459 feet from S Section Line, 4029 feet from E Section Line
Lease/Unit Name: MLP CORNELL UNIVERITY Well Number: 1
County: STEVENS Total Vertical Depth: 6270 feet

Operator License No.: 5447
Operator Name: OXY USA, INC.
Address: PO BOX 27570
HOUSTON, TX 77227

10/31

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 1720 WITH 400 SX CMT
Production: Size 5.5 feet: 6262 WITH 475 SX CMT
Liner: Size feet: 203.7

Well Type: GAS UIC Docket No: Date/Time to Plug: 10/31/2000 10:00 AM
Plug Co. License No.: 6547 Plug Co. Name: SARGENTS CASING PULLING SERVICE
Proposal Rcvd. from: DON HORTON Company: SARGENTS CASING PULLING SER Phone: (316) 697-2500

Proposed Plugging Method: BOTTOM PLUG PUMP 300# HULLS & 25 SX CMT. 1ST PLUG AT 900' WITH 25 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 10/31/2000 2:00 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

DV @ 3097' WITH 200 SX CMT. PERFS AT 5827-5837 & 5856-67'. 1ST PLUG PUMP 3 SX HULLS & 25 SX CMT. 2ND PLUG AT 874' WITH 25 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 0-40' WITH 10 SX CMT. GOOD CIRCULATION THROUGHOUT JOB.

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 874' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

[Signature]
(TECHNICIAN)

INVOICED

DATE 11/3/00
2001060931

OCT 31 2000

[Handwritten initials]

RECEIVED
STATE CORPORATION COMMISSION

10/31 2000

Conservation Division
Wichita, Kansas

[Handwritten signature]

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Oxy USA, Inc.

ADDRESS 1701 N. Kansas PO Box 2528 Liberal, KS. 67905

PHONE (316) 629-4200 OPERATORS LICENSE NO. 5447

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-30-00 (date)

by Scott Alberg (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 5827 Bottom 5867 T.D. 6270

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				<u>8 3/4</u>	<u>1720</u>	<u>—</u>
				<u>5 1/2</u>	<u>6267</u>	<u>874</u>

NOV 22 2000

CONSERVATION DIVISION
 Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each set.

Mixed 3 SX hulls & 25 SX cmt. to plug perfs from 5827 to 5867. Recov. 874 5 1/2 Circ. hole w/mud 25 SX 874 to 800 40 SX 600 to 500 10 SX 40 to 0 Cut off & capped 8 3/4 3 ft below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA INC.

STATE OF Kansas COUNTY OF Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) 1701 N Kansas PO Box 2528 Liberal, KS.

SUBSCRIBED AND SWORN TO before me this 21st day of November, 192000

Anita Peterson
 Notary Public

My Commission Expires: Oct. 1, 2001

