

90102

A-4-114

MAP NO. _____ ELEV. 3244KB, 3241DF
 STATE Kansas COUNTY Morton SEC. 20 Twp 32S Rge 39W
 OPERATOR Pan American Pet. Corp. LOC. C SE NW
 I. NO. 1 FARM NAME Drew GU "D" FT. FROM _____ LINE _____
 COL. Kinsler, SE, Ext. (PD 6000) FT. FROM _____ LINE _____
 FR. 3-6-61 SPUD. 3-5-61 COMP. 4-12-61

CONT./GEOL. Big Chief Tools

NAME PRODUCING INTERVAL COMPLETION RECORD TREATMENT RECORD
 FROM — TO PERF. W/HOLES
Morrow 5505 SI 8 F/10x8

b. New sd.

c. _____

d. _____

d I. P. OIL/DIST. WTR WHOF GAS 4000 M.C.F.P.D. _____ CHK. _____ HRS. _____

b. " " " " " "

c. " " " " " "

d. _____

D & A ()

SIP# 1263 FI TP # _____ FI CP# _____ SIBHP _____GOR. _____ GR. _____ PBDT 5645 TD 6050

SIZE DEPTH CASING - CEMENT RECORD
 W/SAX. SIZE DEPTH W/SAX.

10 3/4" 712 700
4 1/2" 6024 700

OPERATOR Pan American Pet. Corp. WELL NO. #1 Drew GU "D" ELEV. 3241 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			Council Grove	2785	
			Pennsylvanian	3135	
			Topeka	3418	
			Missouri	3962	
			Des Moines	4732	
			Morrow	5480	
			Morrow Sand	5788	
			Chester	5982	

Los Set BP @ 5885.

P 16/5797-99, Swb ld/NS, 500 Ac. Swb ld + 109 bbls fm wtr/17

middle 53 hrs, (95,000 ppm). Set BP @ 5645.

P/9/5505, Frac 10,000 wtr X 8000 Sd, Ran 2" tbg to 5471, G

3,200 MCF + ld, FCP 150#.

IP WHOF 4,000 MCF, Est del 2,580 MCF against 700# Line pressure

SIP 1263/32 hrs, from Morrow 5505.

New Zone

LIBERAL TOPS

3244 KB

Winfield 2468 (+776)

Council Grove 2729 (+515) NT

Heebner 3921 (-677)

Lansing 4026 (-782)

Marmaton 4732 (-1488) WLT = wtr

Morrow 5480 (-2236) T 502', Tss 93'

"S-1" 5504 (-2260) 4/7, WHOF 4,000 MCF S1

"S-3" 5788 (-2544) 14/30, swb wtr

Chester 5982 (-2738)

TD 6050

S3 5876 -2632 24/56 wtr.