


12-215W MAP NO. K-82 SEC. 25-32S-39W
 STATE Kansas COUNTY Stevens LOC. C NW
 OPER Anadarko Production Company - Liberal, Kansas FT/FR LINE
 WELL #1 FARM Armstrong "B" L-53208 FT/FR LINE
Panoma Gas Area ELEV. 3207 GR. 3212 DF. 3215 KB
 CONT Wakefield Drilling GEOL. Ron Cook
 CO. INT. 3025¹ CG Test
 F.R. 11-6-64 SPUD 11-11-64 COMP. 12-22-64
 TD 3041 FM. CG PBTD.



Completion Record	PRODUCING FM.	FROM	TO	PERF W/HOLES	TREATMENT

Casing Record	8-5/8" @612' w/400 Sx.		4 1/2" @3024' w/225 Sx.		<u>Data Inc.</u>

(GR Log Tops:)		RTD 3025 ¹ , Log, 4 1/2" @ 3024' w/225 Sx.,
B/Cimm	1722 / 1485	
Kri	2457 / 750	CO 2988, Perf 30/2926-36 (CG), 500A, §
Winf	2524 / 683	1d, § 3/4 BWPH w/sho gas, Sq 2926-36 w/
U/FR	2594 / 613	200 Sx., Perf 8/2897-99, 12/2875-80, 32/
L/FR	2660 / 547	2854-62 (CG) § no sho - nat, 2000A, (10%)
CG	2762 / 445	§ 1d, w/sho gas, Frac 7500 GW x 5000# sd

LTD 3041 / 166 Ga 368,000 CFGPD & 2 1/2 BLWPH/NT, Temporarily Abandoned - 12-14-64 COMPLETED

Liberal Tops

3207 GL

win 2524 + 683

CG 2794 + 413

TD 3041 D & A