



Ricketts Testing, Inc.

API 15-191-22422-00-00

Company A.G.V. CORPORATION Lease & Well No. SALSBERY # 2

Elevation 1198 G.L. Formation TOPEKA Ticket No. 2144

Date 1-30-04 Sec. 13 Twp. 32S Range 4W County SUMNER State KS

Test Approved by ROD ANDERSON Ricketts Representative JIM RICKETTS

Formation Test No. 1 Interval Tested from 2280 ft. to 2335 ft. Total Depth 2335 ft.

Packer Depth 2280 ft. Size 6 3/4 in. Packer Depth _____ ft. Size _____ in.

Packer Depth 2277 ft. Size 6 3/4 in. Packer Depth _____ ft. Size _____ in.

Depth of Selective Zone Set _____

Top Recorder Depth (Inside) 2285 ft. Recorder Number 11027 Cap. 4275

Bottom Recorder Depth (Outside) 2288 ft. Recorder Number 243 Cap. 6000

Below Straddle Recorder Depth _____ ft. Recorder Number _____ Cap. _____

Drilling Contractor ACE DRILLING RIG #1 Drill Collar Length 456 I.D. 2.25 in.

Mud Type CHEMICAL Viscosity 43 Weight Pipe Length _____ I.D. _____ in.

Weight 9.8 Water Loss 11.2 cc. Drill Pipe Length 1797 I.D. 3.25 in.

Chlorides 53,000 P.P.M. Test Tool Length 27 ft. Tool Size. 5 1/2 in.

Jars: Make STERLING Serial Number 404 Anchor Length 55 ft. Size 5 1/2 in.

Did Well Flow? NO Reversed Out NO Surface Choke Size 3/4 in. Bottom Choke Size 3/4 in.

Gravity Oil _____ Main Hole Size 7 7/8 in. Tool Joint Size 4 1/2 XH in.

Blow: STRONG BLOW IN 4 MINUTES INITIAL FLOW PERIOD.

STRONG BLOW IN 11 MINUTES FINAL FLOW PERIOD.

Recovered 522 ft. of MUD CUT SALT WATER

Recovered _____ ft. of _____

Recovered _____ ft. of _____

Recovered _____ ft. of _____

Recovered _____ ft. of _____

Remarks: DST FLUID CHLORIDES 113,000 PPM

RECEIVED
OCT 22 2004
KCC WICHITA

Time Set Packer (s) 4:30 P.M. Time Started Off Bottom 7:30 P M. Maximum Temperature 99°

Initial Hydrostatic Pressure(A) 467* P.S.I. *PLUGGED

Initial Flow PeriodMinutes 30 (B) 34 P.S.I. to

(C) 174 P.S.I.

Initial Closed In PeriodMinutes 60 (D) 1048 P.S.I.

Final Flow PeriodMinutes 30 (E) 179 P.S.I. to

(F) 264 P.S.I.

Final Closed In PeriodMinutes 60 (G) 1047 P.S.I.

Final Hydrostatic Pressure(H) 1174 P.S.I.