

15-116  
 KANSAS GEOLOGICAL SOCIE  
 508 East Murdock  
 Wichita, Kansas  
 DEC 12 1970

GABBERY-JONES, INC.  
 WICHITA, KANSAS  
DRILLERS' WELL LOG

LOVE #6  
50' S of C SW NE Section 13-32S-4W  
 Sumner County, Kansas

Commenced: July 28, 1969  
 Completed: August 7, 1969

OPERATOR - O. A. Sutton

13 32-4W  
 150's, C SW NE  
 PMP 62 BOPD + 71% with  
 Est 1,000,000 C F6PD/5tal  
 KC

Elev. 1249' KB

DEPTH	FORMATION	REMARKS
FROM	TO	
0	60 60	Sand and clay
60	240 240	Red bed and shale
240	270 270	Shale
270	630 690	Shale and lime
690	925 925	Shale and shells
925	3295 3295	Lime and shale
3295	3463 3463	Lime
3463	TD	Ran 8 joints of 10-3/4" casing, set @ 264' w/185 sacks cement.
		Ran 107 joints of 7" casing, set @ 3462', 1' off bottom, w/200 sacks cement.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled 50' S of C SW NE Section 13-32S-4W, Sumner County, Kansas, to the best of my knowledge and belief.

Log Info

STATE OF KANSAS

COUNTY OF SEDGWICK

Tafef	2251
Heebner	2637
Jatan	2973
Stal Sd.	3006
) Kam. City	3276
) SE "C" 3n	3392
) SE Blb Sh	3426
"D" 3n	3442

E. E. Hall

Before me, the undersigned, a Notary Public within and for said County and State, on this 12 day of August, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the