


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PAN AMERICAN PETROLEUM CORP.
 Farm- Hayward GU "C" No. 1

SEC. 2 T. 32 R. 40W
 C SW NE

Total Depth. 6200' PB 2832'
 Comm. 10-14-60 Comp. 11-4-60
 Shot or Treated.
 Contractor. Big Chief Drlg.
 Issued. 10-14-61

County Morton
 KANSAS



CASING:
 8 5/8" 732' cem w/400 sx.
 4 1/2" 6000' cem w/54 sx.

Elevation. 3296' RDB

Production. Dry

Figures indicate Bottom of Formations.

surface sand, clay	344
sand	471
shale, Anhydrite	732
shale, sand	805
redbed, shale	1455
sand, shale	1760
shale, anhydrite	2245
shale	2330
shale, anhydrite	2650
sand, lime	2738
shale, lime	3007
shale, lime, chalk	3150
shale, lime	3744
lime	3814
lime, shale	4738
lime	4797
lime, shale	4905
lime	4960
lime, shale	5348
shale	5450
shale, lime	5896
lime	5985
lime, shale	6024
lime	6055
lime, shale	5142
lime	6180
lime, shale	6200
Total Depth	
Plugged back to 2832'	

TOPS:

Council Grove	2860
Topeka	3392
Missourian	3910
Des Moines	4668
Morrow	5430
Chester (scout)	5866
St. Genevieve (scout)	5966
St. Louis (scout)	6068