

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


23-32-41W

Company- PAN AMERICAN PETRO. CORP.
Farm- Lemon Gas Unit "C" No. 2

SEC. 23 T. 32 R. 41W
C SW

Total Depth. 5300' PB 5265'
Comm. 12-7-57 Comp. 1-27-57
Shot or Treated.
Contractor.
Issued. 5-11-57

County Morton
KANSAS



CASING:
9 5/8" 1487' w/1000 sx cem.
7" 5292 w/1100 sx cem.

Elevation. 3404' DF

Production. Open flow 31,600,000
MCF/D

Figures indicate Bottom of Formations.

SHALE	330
sdv clay	400
red bed	695
red bed-sand	1040
red bed	1150
red bed-anhydrite	1485
anhydrite	1548
red bed	1660
red bed-shale	2165
lime-shale	2805
shale	2980
lime-shale	3275
lime	3340
lime-shale	3453
lime	3585
lime-shale	3662
shale	3770
lime-shale	4160
lime	4229
lime-shale	4353
lime	4515
lime-shale	4560
lime	4723
shale-lime	4870
shale	4895
shale-lime	5000
shale	5060
lime	5110
shale-lime	5121
shale	5125
shale-lime	5225
lime	5300
Total Depth PB 5265'	

DST #1 - 3130-3245'. Open 1 hr.,
closed 1/2 hr. Fair blow. Rec. 40'
mud. No show gas. BHP 510#. HH 1570#.

DST #2 - 5200-5300'. Open 1/2 hr.,
closed 1/2 hr. Gas to surface in
3 min. 30 min. gauge 5660 MCF/D.
Rec. 130' GCM & 180' distillate &
GCM. FF 1310#, BHP 1310#. HH 2710#.

Perf. 5200-10' & 5221-29'
Perf. 5162-68'
Perf. 5132-37'
Perf. 5098-5106'

Fraced w/15,000 gal. wtr.
" w/15,000 gal. wtr.

Ran Schlumberger.

TOPS: Schl.
Topeka 3118
Des Moines 4227
Morrow sand 5052
Keyes sand 5195
Mississippian 5250