


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PAN AMERICAN PETROLEUM CORP.
Farm- Murphy GU "C" No. 1

SEC. 14 T. 32 R. 41W
C NW

Total Depth. 5400' PB 5179'
Comm. 1-30-62 Comp. 3-21-62
Shot or Treated.
Contractor. Barbour Drlg.
Issued. 7-7-62

County Morton
KANSAS



Elevation. 3357' DF

Production. 2,136,000 CFG

CASING:

8 5/8" 1509' cem w/750 sx.
5 1/2" 5244' cem w/200 sx.

Figures Indicate Bottom of Formations.

sand-clay	136
sand-clay-redbed	455
sand-redbed	940
redbed-shale	1445
Anhydrite - lime	1514
sand-redbed	1627
shale	1845
shale - lime	2500
lime	2822
shale - lime	3275
lime	3830
lime-shale	4000
lime	4575
lime-chert	4616
lime-shale	5200
lime	5400

Total Depth
Plugged back to 5179'

TOPS: SCOUT

Krider	2120
Winfield	2173
Wabaunsee	2843
Topeka	3106
Gr. Lansing	3430
Lansing	3646
Morrow	4795
Morrow Sand	5084-5101
Morrow Sand	5143-72
Lower Sand	5202-06
Keyes	5232-46
Mississippi	5265
St. Geneveive	5309
St. Louis	5368