

PANHANDLE EASTERN PIPE LINE COMPANY

Going 1-26
C of SE/4
Section 26-32S-41W
Morton County, Kansas

Formation Tops

Marmaton	4238'
Cherokee	4404'
Morrowan Shale	4758'
Lower Morrowan Ss.	5078'
Lower Morrowan Ss.	5120'
Lower Morrowan Ss.	5159'
Lower Morrowan Ss.	5191'
Mississippian	5230'
Total Depth	5280'

Completion Information

Spud July 14, 1956.
Set 1484' of 8 5/8" casing with 850 sacks cement.
Set 5279' of 5 1/2" casing with 800 sacks cement.
Cleaned out to 5258'.
Perforated 120 holes 5192-5222'.
Gauged 10,375 MCF.
Acidized 1000 gallons 15%.
Fractured 15,000 gallons oil and 15,000# sand.
Open flow gauged 61,944 MCF.

Completion Test: September 21, 1956.
Calculated open flow 97,800 MCF
from Lower Morrowan Sandstone
5192-5222'.