


State Kansas Field WILDCAT
 Company PEPL County Morton
 Farm Going No. 1-26
 Sec. 26 Twp. 32 Range 41

Spot C SE

Contractor _____

Remarks Miss. Test



Comm. 7/14/56 Comp. 10/2/56

Elev. (DF) 3418 (GI) 3411 (KB) 3421 TD 5280 PB _____

Pay 5192-5222

I.P. COF = 97,800 MCF Press. 1169 #

Casing Record: 13 3/8 _____ 7" _____

20" _____ 10 3/4 _____ 5 1/2" 5279/200

16" _____ 8 5/8 1484/850

JUL 18

8 5/8 1484/850 WOC

Sample

Log

July 25; DST 3152-76 op
 45" qts 7" 12" g 132 MCF
 27" 232 MCF 45" g 277 MCF
 Rec 70' mud FP 140 BHP 500/20
 \$ 3510

Kri 2160

Wing 2216

UTRI 2290

Wnt 2878

Top ⁺²⁹⁶ 3122

Jan. 3652

Marm 4238

Ck 4404

Mor 4758

Mor ss 5040

"6" ad 5159

Kays 5191

Miss 5230

DST #2 4286-4317 op 1 hr.
 qts 3" g 490 MCF in 5"
 666 MCF in 35" g 723 MCF
 in 60" rec 15' gcm. FP 90
 BH 980/20

DST (L Marm) 4364-4413 op 45"
 qts 1 1/2" g 1,022 MCF in 5"
 1,372 MCF in 15" g 1,634 in
 45" rec 10' gcm. FP 240
 BHP 1030/20

DST 4434-4500 op 1 hr. Vard blo. rec
 10' plng gcm Press 0
 \$ 4580

AUG 8

DST 4769-4823 op 45" rec 50' mud press 0
 DST 5066-5130 op 65" qts 3" g 1,862 MCF
 in 15" g 2,128 MCF in 30" 2,192 MCF in 40"
 2,252 MCF in 50" rec 310' gcm + 120' salty
 gcm FP 460 2560 BHP 1170/25

DST 5142-80 ap 20" GTS 2" @ 2,544 MCF
in 10" @ 4,732 mcf in 15" no rec.
FP 570 BHP 1300/20

DST 5197-5230 ap 20" GTS 1" @ 2,780
mcf in 4" @ 9,260 mcf in 10" run 2'
dist. FP 1300 BHP 1630/20

RTD 5280 now log 5279 set 5 1/2
5279/800.

AUG 15 EUCT CO to ? Run 2 7/8 to 5213
of 120/5192-5222 SI 6 hrs. 20" OF @
10,375 mcf. RP 1050# pte to heat.

8-22-56 A/1000 15%, SI 6 hrs. gauge 11,712 MCF
RP 1150#, frac 115,000 pers, sd/115,000, SI 6 hrs
op 1 hr, gauge 13,350 MCF thru thg. CP 1050#
gauge O.F. 61,944 MCF, drying up, SI, W.O.T.

AUG 29 NOT.

SEP 5 ✓ SEP 12 ✓ SEP 19 ✓ SEP 26 ✓

OCT 3 C.O.F. = 97,800 MCF + 8.94 bbl dist per MCF
R.P. 1169#

Ⓢ

State test

CW HOF 97,800 MCF

RP 1169#