

3-359

MAP NO.

82

SEC.

14-32S-41W

STATE Kans

COUNTY

Morton

LOC.

C NW/4

OPER. Pan American Pet. Corp.

FT/FR

LINE

WELL 1

FARM

Murphy GU "B"

FT/FR

LINE

POOL Richfield

ELEV. 3349

GR. 3357

DF 3360

KB

CONT. Barbour Drlg Tools

GEOL.

CO.

IT.

R. 1/31/62

SPUD

1/13/62

COMP.

4/3/62

TD. 5401

FM.

PBTD.

PRODUCING FM.

FROM

TO

PERF
W/HOLES

TREATMENT

Morr

5144-46

8

Frac

COMPLETION RECORD

PROD. INTERVAL
& TREATMENT

PROD. FM-1 P.

Est Del Ga 1200 Mcf/gpd/24 hrs, Morr 5144-46CASING
RECORD

SIZE

DEPTH

SAX

SIZE

DEPTH

SAX

8-5/8"

1540

750

5-1/2"

5244

300

OPER. Pan American Petr.

SEC.

14-32S-41W

WELL 1 Murphy GU "B"

ELEV 3360 KB

LOC.

C NW/4

RTD (St Gen) 5400

KB Tops & Datums

Mo 3586 - 226

Des M 4241 - 881

Morr 4796 - 1436

Morr Marker 5082 - 1722

Morr Sd 5142 - 1782

Chest 5264 - 1904

St Gen 5308 - 1948

LTD (St Gen) 5401 - 2041

WLT #1 (Morr) 5143, Op 1

hr, R .01 cfg + 6750

cc wtr, IBHP 1200#/24",

SP 650#, FBHP 1000#/20".

WLT #2 (Des M) 4555, Op 30"

R 1.9 cfg + scum Oil +

18,750 cc wtr, IBHP

1250#/2", SP 0-85#,

FBHP 1200#/6".

RTD 5400. Log. 5 1/2" @ 5244 w/300 sx. CO 5179 PBTD

8/5144-46 (Morr) Swb dry nat, Frac (20,000 GW x

6,000# sd), Flo 175 B ld/24 hrs, Ga 2930 Mcf/gpd/9

hrs, Ga 3310 Mcf/gpd/10 hrs, Ga 2,563 Mcf/gpd + 4 BLWPH

7 hrs, Pkr 5087, 8/4554-56 (Des M) Swb dry, 1000 A,

(15%) Swb ld, Swb SSO & G, 3000 A (15%) Swb 160 B ld

10 hrs, no inc oil or gas, sq 4554-56 w/75 sx, CO

5179 PBTD, WH OF Ga 2,136 Mcf/gpd, Est Del Ga 1200

Mcf/gpd @ 700# line press. Morr 5144-46 COMPLETED

LIBERAL ELECTRIC LOG TOPS

3360 KB

Topeka 3106 (+254)

Lansing 3636 (-276)

Marmaton 4168 (-808) \$ 1d w/SSO&G (Cherokee)

Morrow 4796 (-1436)

"S-3" 5082 (-1722) 3/40, NT

"S-3" 5142 (-1782) 20/30; ϕ 1,200 MCF

Keyes 5240 (-1880) 4/8; NT

Chester 5248 (-1888)

Ste. Gen 5308 (-1948)

TD 5400