

**** OFFSET

4

State Kansas Field Greenwood
County Morton
Company Colo. Oil & Gas
Farm McGuire Well No. 1-3
Sec. 3 Twp. 32S Range 42W
fr N fr E fr S fr W
of C NW $\frac{1}{4}$

Contractor

Remarks

Comm. 5-22-55 Comp. 6-29-55
Elev. 3506 D.F. T. D. 3617 P. B.
Pay 3504 2806-2835, 2916-86 NO?
NO? 3106-74

I. P. 19,611 mg R. P. 465#

Casing Record: 13 3/8 7
20 10 3/4 51/2 3288/400
16 85/8 635/400
log to Co

	5-25-55	WOC.	Tops
JUN 1 1955	<u>Ø 2540</u>		<u>Walt 2791</u>
JUN 8 1955	<u>DST #1 2793-2842</u>		<u>Elmont 3030</u>
	<u>Ø 1/4 in. g/s in 2 min</u>		<u>Top + 300 3204</u>
	<u>g = 1935 WCY</u>		
	<u>rec 57' gcm, FP 440-440</u>		
	<u>BH 440/30</u>		
	<u>DST #2 2858-2925</u>	<u>Ø 2 in.</u>	
	<u>whble dned in 30 min</u>		
	<u>rec 100' gcm FP 0-50</u>		
	<u>BH 440/30</u>		
	<u>DST #3 2944-3025</u>	<u>Ø 2 in.</u>	
	<u>whble to g in 75 min</u>		
	<u>rec 110' gcm FP 50-100</u>		
	<u>BH 440/30</u>		
	<u>DST #4 3207-29</u>	<u>Ø 2 in. g/s.</u>	
	<u>in 1 hr. rec 118' gcm, FP 0-50</u>		
	<u>BH 440/30</u>		

DS 45 3592-3617 of 2 hrs. of 6/6
down after 1 1/2 hrs. rec 165' msw, 840' SW
FP 350-350 BH 680/

RTD 3617 30
ran log @ 3617 run 1/2 3288/400

MIC T CO to 3257
P 22/3229-45 (with net)
log w/ph. & egg w/35 m

CO to 3227

Q 12/3204-10 A/1200

JUN 16 1955

Q - 125 gwph - g tstr
log w/ph @ 3180 & egg w/95 m
CO to ?

P 18/3163-74, 6/3135-38, 12/3106-12

A/4000 g 477 mg w/60 gwph
g 475 " " 2 gwph
plug @ 3050

P 18/3005-14, 6/2983-86, 6/2976-79

A/3000 g 477 mg w/25 gwph

plug @ 2925

P 16/2862-70, then to A/8/2906-08
A/3000

JUN 22 1955

A/3000 g - 60 gwph

ph @ 2848 & egg w/40 m, CO to 2925

P 52/2822-35, 8/2815-17, 16/2806-10, A/4000

g - 14,263 mg w/spray. knocked plug
g - 15,417 mg w/spray

JUN 29 1955

12/20 19,611 mg

RP 465 #