


# FARMOUT

State Kans. Field Greenwood  
 Company Graham Michaelisa County Morton  
 Farm Maguire corr. Baughman No. 1  
 Sec. 1 Twp. 32 Range 42

Spot CWU  
 Contractor Co Tools  
 Remarks RD 3300, sup. F.O.



Comm. 1-15-57 Comp. 3-3-57  
 Elev. DF 3460 GL 3454 KB TD 3300 PB 3251  
 Pay 2831-65  
3030-94, 3142-3208

I.P. 72/20 5,000 MCF Press. R.P. 425  
 Casing Record: 13 3/8 ..... 7"  
 20" ..... 10 3/4 ..... 5 1/2" 3277/100  
 16" ..... 8 5/8 635/300

Log	Sample	Log
<del>JAN 2 3</del>		<del>wal 2827</del>
<del>635 @ 635 / 300</del>		<del>Elev <sup>384</sup> 3076</del>
<del>2732</del>		<del>TD @ 3296</del>
JAN 3 0		
RTD 3300 <u>5 1/2 @ 3277/100</u>		
new log. <u>woc</u>		
FEB 6		
RUCT CO 3251, Pf 16/		
3204-08, 16/3187-91,		
16/3162-66, 16/3142-46		
A/1000 m, swab g 700MCF,		
A/4000 swab g 700MCF,		
A/600 w/60 balls, g		
700MCF, <u>Testing</u>		
FEB 1 3		
swab 736 MCF pl @ 3090 pf 24/3088-99		
16/3050-02, 24/2042-40, 16/3030-34 pk 3050		
A/6000 <u>Testing</u>		
Swab gas 2 1/2 Bwph No gas, pl to TD, pl @ 2966		
Pf 16/2934-38, 16/2912-16, 12/2902-05,		
12/2890-93, A/1000 m, swab 100 gw ph No gas,		
T 4 pk @ 2879 24/200, pf 12/2862-65,		
8/2868-60, 12/2842-45, 20/2833-38		
12/2821-24, swab, A/1000 m		

5/1 sho gas. ~~Deep to st pk; test east core~~  
~~up to A<sub>2</sub>~~

FEB 20

~~2950  
1000  
500 MCF  
1000~~

DP1 TO TD - use straddle packers to

A/2862-65/1000, A/2858-60/1000, A/2842-45/  
1000, A/2833-38/1000, best pk, fished out,  
A/2821-44/1000, sho gas, swab 200 g w ph,  
zone 3144-3210 g 1,131 MCF, A/3144-3210/4000  
g 500 MCF, Lat g 600 MCF. M.O.C.T. **Testing.**

FEB 27

MAR 6

72/20 5,000 MCF  
R.P 425

φ