

★★★★


6

State Kansas Field Glennwood
 Company Skelly County Morton
 Farm A. W. Hines No. #1
 Sec. 10 Twp. 32S Range 42W

Spot C NW

Contractor DAN FOLTH

Remarks



Comm. 7/31/56 Comp. 10/10/56

Elev. DF 3506 GL 3498 KB TD 3260 PB 3221

Pay ~~3214-3206~~ 3214-3206, -3158-66, 3130-34, 3099-3104
2889-96, 2848-66, 2823-27, 2802-13

I.P. COE 6, 0.58 MCF Press.

Casing Record: 13 3/8 7"

20" 10 3/4 5 1/2" 3260/150

16" 8 5/8

Sample	Log (KB)
<u>475</u>	<u>Admire 2658</u>
	<u>Web 2858</u>
	<u>Elmout 3032</u>
	<u>Topeka 3198</u>

AUG 8 ret 18 1/2 686/400

2586

AUG 15 RTD 3260 ran log

5 1/2 3260/150

Aug 22 MCT.

AUG 29 CO 1 3250 pf 30/3242-47 g

84 mcf + 36 g swph set pl 3239 pf 60/3226-36

4 hr g 21.5 mcf gas 30 g swph pl 3223 pf.

42/3214-21 g 44 mcf. pf 42/ 3199-3206

g 108 mcf. A/1000 g 196 mcf + 25 g swph

A/3000 8 hr BD g 300 MCF + 35 g swph.

set pl 3179 pf 48/3158-66 g 108 MCF A/1500

7 hr g 636 mcf. + 3 bbl swph set pl

3140 pf. 24/3130-34 A/1000 12 hr BD

g 520 mcf + 2 bbl swph of pla CO

to 3223 11 hr BD g 424 mcf + 100

g swph. 8 hr SIP 420 g gl bbl 200

A/4000 9 hr BD g 600 MCF + 100 g swph

SEP 5 ret pl @ 3116 pf 30/3099-3104 36/3002

08 ran T wph @ 3012 A/1500 A/1500

ran T wph to 3000 3 hr BD g 1,002 mcf

24 BD g 908 MCF 1 bbl swph

ret pl @ 2808 pf 42/ 2888-96

48/2858-66 54/2843-52 Twp @ 2875
A/2000 A/1000 pulled Twp 7hr BD
1,041 mcf. dry. - set pl @ 2833 pf
24/2823-27 gas 2,016 MCF dry. pf 18/
2810-13 24/2802-06 A/3000 8 hr BD
2,354 mcf + 1 Mbl swph. fall pl 50
to 3221 gas 2,500 MCF non T to 3220
51 NOT

SEP 12 / SEP 19 ✓ SEP 26 ✓ OCT 3 ✓ OCT 10 ✓

~~12~~ BD 3,080 MCF

FCP 315#

ADF 6,059 MCF

SICP 430#

⊕