

MAP NO. 1-3-60 ELEV. 3555DF, 3557 KB
 STATE Kansas COUNTY Morton SEC. 19 Twp 32S Rge 42W
 OPERATOR Cities Service Oil Co. LOC. App C SE/4
 WELL NO. 1 FARM NAME Matson matzen 1390 FT. FROM E LINE
 POOL Greenwood Gas 1250 FT. FROM S LINE
 FR. 11-11-60 SPUD. 11-10-60 COMP. 1-3-60

CONT./GEOL. Tommy Ward Tools

COMPLETION RECORD			
NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a. <u>Topeka</u>	<u>2992-3182</u>	<u>162</u>	<u>27,750 Ac</u>
b. <u>Lansing</u>	<u>3210-22</u>	<u>48</u>	<u>500 Ac</u>
c. _____	_____	_____	_____
d. _____	_____	_____	_____

a. I. P. OIL/DIST. WTR NW GAS 17,500 M.C.F.P.D. COF CHK. _____ HRS. 24

b. " " " " " " " "

c. " " " " " " " "

d. " " " " " " " "

SIP# 316.8 FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBTD 3247 TD 3280

SIZE		DEPTH	CASING - CEMENT RECORD		DEPTH	W/SAX.
SIZE	DEPTH	W/SAX.	SIZE	DEPTH	W/SAX.	
<u>8 5/8"</u>	<u>598</u>	<u>325</u>	_____	_____	_____	_____
<u>4 1/2"</u>	<u>3279</u>	<u>225</u>	_____	_____	_____	_____

OPERATOR Cities Service Oil Co. WELL NO. #1 Matson ELEV. 3557 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Topeka	2948				
Lansing	3208				

Spud 11-10-60, 8 5/8" @ 598 w/325 sx. RTD 3280, Ran (Sj), 4 1/2" @ 3279 w/225 sx. RUCT, CO to 3247.
 P/48/3210-22, NS Nat, 500- 15% Ac, Rc load, Ga 1840 MCFG/27hrs. Set BP @ 3200.
 P/8/3180-82 & P/16/3164-68 (Topeka) NS, Nat., 750 - 15% Ac, Rc 1d, Swb SSG + 5 GAWPH/9 hrs, ga, TSTM.
 P/60/3095-3110 (Topeka), P/16/3046-40, P/24/3022-38 (Topeka), P/24/3012-18 (Topeka), P/24/2992-98 (Topeka), Ga 1300 MCFG Nat, 5000 - 15% Ac, Rc 1d, Ga 6580 MCFG/8 hr BD, 1500 - 15% Ac. Set BP @ 3200, Ga 7010 MCFG (Topeka & Lansing) 20,000 Ac, Rc 1d, Ga 10,200 MCFG/4 hrs, Set BP @ 2980.
 P/12/2912-18, 500 - 15% Ac, Ga 196 MCFG + 10 GSWPH above 1d. Sq P/2912-18 w/100 sx.
 P/8/2752-56, SG/TSTM + 2 GWPH/8 1/2 hrs, Sq P/2752-56 w/ 70 sx. CO to 3247 PBD, Ga 10,200 MCFG/20 hrs

3527 KB

255B KB

679-352