



ROBINSON OIL COMPANY

R. H. GARVEY BUILDING • 300 WEST DOUGLAS • WICHITA, KANSAS 67202 • (316) 262-6734

18-32-5W

WELL DATA FOR PLUGGING PURPOSES

WELL NAME: HALLMAN NO. 1
LOCATION: SE NW NW Sec. 18-32S-5W
COUNTY: Harper

WELL DATA

TD 4712

PBTD 4712

SURFACE CASING 8-5/8" @ 266' w/250 sax cement

LONG STRING 5 1/2" 14# J55 (new) @ 4712'

CEMENT JOB 150 sax common w/5% salt & 2% gel

TOP OF CEMENT 3720' by Cement Bond Log

PERFORATIONS Open Hole - 4707' to 4712'

TYPE OF WELL Oil well - went to 99% salt water

PLUGGING PROCEDURE Plug back to 4650' w/sand. Dump 4 sax cement
@ 4650'. Shoot off 5 1/2" @ 3700'. Pull 5 1/2" casing. Bail down to
320'. Plug hole from 320' up to 5' B.G.L. w/6 yds. of Redi-Mix.

ADDITIONAL INFORMATION From Danville go 1 mile west, 1/4 south,
1/4 east. Name of tenant is Jim Robb.

RECEIVED

STATE OF KANSAS

DEC 21 1987

DEC 15 1987

CONSERVATION DIVISION
Wichita, Kansas

KANSAS GEOLOGICAL SURVEY
WICHITA BRANCH

ROBINSON OIL COMPANY
by: Dale M. Robinson
Dale M. Robinson