

20" 10"
 15 1-2 8 1-4
 12 1-2 6 5-8
 5 9-16

 FARM Burke
 COMPANY Berry Petroleum Co.
 CONTRACTOR
 COMMENCED 9-27-25.

COMPLETED 5-27-1927.

TOTAL DEPTH 4425'.

SHOT

QUARTS BETWEEN

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO

ELEVATION 1332

INITIAL PRODUCTION Dry.

FIGURES INDICATE BOTTOM OF FORMATIONS.

REMARKS 9/10/27.

Formation	Depth	Formation	Depth	Formation	Depth
red rock	35	shale	1725	lime	3025
gravel	40	lime	1740	shells	3055
red rock	260	shale	1755	lime	3060
shale	265	sand	1767	broken lime	3110
red rock	340	lime	1780	shale	3130
shale	345	sand HFW	1820	sandy lime brkn	3140
red rock	370	lime	1838	sand	3155
shale	685	shale	1845	lime	3180
salt	690	lime	1875	broken lime	3195
shale	700	sand	1898	sand	3240
red rock	705	slate	1940	shale	3410
salt	730	lime	1951	lime	3415
shale	735	shale	1956	sand HFW	3500
lime	740	lime	1980	lime	3510
salt	790	shale	1990	shale	3625
shale	800	lime	1996	lime	3665
salt	830	sandy shale	2005	broken lime	3675
shale	900	broken lime	2025	sand HFW	3690
salt	910	shale	2040	sandy lime	3700
shale	920	sandy shale	2065	lime	3740
lime	930	lime	2080	sandy lime	3750
salt	935	shale	2095	brown lime	3765
shale	940	lime	2100	sand	3780
salt	950	shale	2155	lime	3790
shale	975	lime	2165	No record to	3820
lime	985	shale	2220	white lime	3845
shale	990	lime	2225	brown lime	3855
lime	1015	shale	2230	black lime	3905
shale	1050	lime	2235	black shale	3910
shale & lime shell	1125	shale	2245	lime	3915
lime	1140	lime	2250	black shale	3930
shale	1150	shale	2282	white shale	3945
lime	1175	lime	2287	broken lime	3950
shale	1180	sand water	2305	lime	3952
lime	1193	lime	2325	broken lime &	
sand	1195	shale	2335	shale	3965
lime shells	1205	lime	2342	lime	3970
shale	1230	shale	2355	black shale	3985
lime	1260	lime	2365	red rock	3992
shale	1270	shale	2375	broken lime &	
lime	1320	lime	2390	variegated shale	4000 SLM
shale	1345	shale	2393	Various colored shale	
lime	1365	lime	2430		4028
shale	1375	shale	2472	lime	4038
lime	1435	lime	2540	slate	4050
shale	1455	broken lime	2575	sand stone	4057
lime	1460	shale blue	2595	HFW 4055-57'	
sandy lime	1475	lime	2600	sandy lime	4060
lime	1500	shale blue	2650	lime	4065
shale	1505	lime white	2695	slate	4070
sandy lime	1515	broken lime	2700	sandy lime	4079
shale	1530	sandy lime HFW	2705	lime	4085
lime	1540	lime	2790	black slate	4089
shale	1550	shale	2795	lime	4130
lime	1595	lime	2810	sandy shale	4150
shale	1600	shale	2830	broken lime	4160
red rock	1615	lime	2855	shale variegated	4170
lime	1655	shale	2860	shale variegated	4270
sandy lime	1675	lime	2875	blue shale	4300
shale	1680	shale	2890	variegated shale	4325
lime	1690	sand	2905	sand Lime	4333
shale	1700	black shale	3010	lime	4341
lime	1720	shale	3020	chat	4360

(over)

Burke No. 1

Sec. 19-32-5 West.

Formation

Depth

sandy lime	4362
sand	4370
chat	4375
sand	4380
sandy lime	4383
lime	4420
lime	4425
Total Depth	4425'
Dry.	