

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

22-32-5W

COMPANY DRILLERS PRODUCTION

SEC. 22- T. 32 N. 5W
LOC. NE SW NE

FARM Fulton Estate NO. 1

TOTAL DEPTH 3380'

COMM. 6-20-66

COMP. 6-29-66


SHOT OR TREATED

CONTRACTOR Gabbert-Jones

ISSUED 9-3-66

COUNTY Harper

KANSAS



CASING

20	10
15	8 5/8" 220' cem w/ 200 sx
12	6
13	5

ELEVATION 1287' KB

PRODUCTION DRY (Stal)

FIGURES INDICATE BOTTOM OF FORMATIONS

DEPTH		FORMATION	REMARKS
FROM	TO		
0	80	RED BED AND SHALE	RAN 6 JOINTS OF 8-5/8" CASING, SET @ 220' w/200 BAGGS CEMENT.
80	220	RED BED	
220	740	RED BED AND SHALE	DRY AND ABANDONED.
740	860	SHALE	
860	1125	ANHYDRITE, SHALE AND SHELLS	
1125	1255	LIME	
1255	1385	LIME AND SHALE	
1385	1500	LIME	
1500	1855	LIME AND SHALE	
1855	2020	SHALE AND SAND	
2020	2025	LIME	
2025	2975	LIME AND SHALE	
2975	3080	LIME	
3080	3360	LIME AND SHALE	
3360	3380	SHALE AND SAND (CORE)	
3380	TO		

TOPS: SMP
Indian Cave 1979
Pennsylvanian 2020
Elmont 2251
White Cloud shale 2401
Howard 2435
Severy 2525
Topeka 2617
Heebner 2995
Douglas 3084
Iatan 3330
Stalnaker 3367