


Company- MORRISON DRILLING CO.
 Farm- Himmers No. 1

SEC. 31 T. 32 R. 5W
 NE NE NE

31-32.5W

County Harper

KANSAS



Total Depth. 4846.5

Comm. 11-11-52

Comp. 12-16-52

Shot or Treated.

Contractor. Morrison Drilling Co.

Issued. 2-14-53

CASING:

5 1/2 3780'

Elevation. 1342

1345 (cond)

Production. Dry

Figures indicate Bottom of Formations.

surface, plug & cement	166
red bed & shells	875
shale & shells	1100
shale & broken lime	1200
lime & shale	1650
lime	1780
shale & lime	2295
lime & shale streaks	2390
lime & shale	2652
lime	2820
lime & shale	3090
shale & lime shells	3134
shale & lime streaks	3195
sandy lime	3255
sandy shale & lime	3348
lime & shale	3477
sand & lime	3535
shale	3540
lime & shale	3702
lime	3940
lime & shale	4048
shale	4143
lime & shale	4179
shale & lime streaks	4218
shale & lime	4280
shale & lime streaks	4335
shale	4352
cherty lime	4363 1/2
lime	4645
shale & lime streaks	4681
lime	4705
shale & lime	4725
shale	4807
sand	4846 1/2
Total Depth	

SCOUT-TOPS:

Lansing	3431
Stalnaker	3477
Kansas City	3719
Mississippi	4360
Kinderhook	4703
Chat	4785
Simpson dolomite	4801
Simpson sand	4805
Hard sand	4838