

Location NW NW NW

Plotted

19-32-6W
Sec. 19 T. 32 R. 6W

DEC 23 1929

Casing Record

Farm- Thompson

No. 1

County - Harper

20" 10"

15 1/2" 8 1/2"

12 1/2" 65/8"

12 1/2" 53/16"

Total Depth 5142

Company- T.B. Slick

Contr.-

Comm.- 6-20-29

Comp.- 12-7-29

Shot

Quarts Between

Correspondence Regarding This Well Should Be Referred to

Elevation 1448

Initial Production Dry

Figures Indicate Bottom of Formations.

Date Issued. 12-21-29

Formation	Depth	Formation	Depth
clay sand rock	56	shale	4134
Set 56' surface pipe.		slate	4144
shale & shells	541	shale & lime shells	4224
shale	575	lime & shale	4238
lime	580	shale & lime shells	4340
shale & shells	1572	lime & shale	4489
brkn lime	1682	shale & lime shells	4573
lime	1772	sdv lime	4613
brkn lime	1900	Run 8 1/4" casing.	
brkn lime	1960	Drilled plug & hole FW.	
shale & shells	2010	hrd sdv lime	4689
shale & lime shells	2180	Corrected measurement from	
shale & lime	2255	4613-4677'.	
shale & shells	2345	sdv lime	4705
shale & lime	2410	sdv lime gray	4723
shale	2440	hrd gray sdv lime	4741
shale & shells	2540	hrd sdv gray lime	4774
shale & shells	2570	sdv lime	4816
lime	2600	shale blk	4866
shale & shells	2715	slate blk	4883
shale	2820	lime brown & blk shale	4895
shale & shells	2900	shale blk & lime	4905
brkn lime	2920	lime blk	4907
shale	2930	shale blk	4919
sand lime	2950	slate blk	4930
shale	2960	shale blk	4940
lime	2995	lime	4945
shale lime shells	3035	lime & sand	4950
lime & shale	3065	4947-50 brown sand, little	
shale	3075	showing of oil shut down	
sand lime	3085	for 6" csg. Cemented 6-5/8" csg.	
shale	3105	Pipe measurement 4978'.	
shale shells	3230	sand HFW	4980
shale & lime shells	3278	sand	4983
sdv lime	3290	sdv lime	4990
shale & shells	3318	sand gray fine	5050
shale shells	3328	sand gray fine	5060
sand	3332	shale brown	5065
lime & slate	3360	shale green	5070
shale & shells	3380	shale blk	5080
lime	3390	shale blk	5120
shale & shells	3415	shale & slate	5130
shale blk	3450	shale sdv	5142
lime	3454	Hole full water.	
slate hrd	3465		
shale & slate	3575	Total Depth	5142
lime	3580		
shale & slate	3630		
shale	3646		
sand	3650		

Cored wtr sand & shale,
slate.

sand	3680
lime & sand	3715
blk shale & lime	
shells	3795
lime & shale	3892
shale	3905
shale & shells fine	3915
shale brkn lime	3980
shale & hrd lime	4025
lime	4050
shale & shells	4080
shale & lime shells	4110