

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


4-32-7W

Company- BOA & WALTERS
 Farm- Muir "B" No. 1

SEC. 4 T. 32 R. 7W
 NW NW NE

Total Depth. 4736'
 Comm. 12-16-60 Comp. 12-29-60
 Shot or Treated.
 Contractor. Walters Drlg.
 Issued. 3-25-61

County Harper
 KANSAS



CASING:
 8 5/8" 215' cem w/175 sx.
 4 1/2" 4734 1/2' cem w/150 sx.

Elevation. 1455' KB

Production. 120 BOPD

Figures Indicate Bottom of Formations.

soil & clay	15
sand	35
red rock & shale	215
shale & shells	1210
lime & shale	1430
lime	1825
lime & shale	3089
sand	3100
sand & shale	3185
shale & lime	3590
sand & shale	3665
lime & shale	3895
lime	4005
lime & shale	4385
Mississippian	4400
Miss. lime & chert	4606
lime & shale	4685
shale	4731
sand & shale	4733 RTD
sand & shale	4736
Total Depth	

TOPS: SCOUT	
Elgin Sand	3085
Heebner	3233
Stalnaker Sand	3591
Kansas City	3816
Base Kansas City	4025
Mississippi	4367
Base Mississippi	4618
Chattanooga	4695
Misener	4732
Simpson	4734