


Total Depth. 4770'
 Comm. 9-14-59 Comp. 9-29-59
 Shot or Treated.
 Contractor CO Tools
 Issued. 12-26-59



CASING:
 8 5/8" 214'

Elevation. 1469 KB

Production. DRY

Figures Indicate Bottom of Formations.

clay & sand	40
red rock & sand	115
" " & sandy strks.	215
" " , Red Beds, shale	550
shale	750
Anh.	765
shale	1105
shale & shells	1160
salt	1200
lime & shale	1355
lime w/shale	1610
lime	1870
lime & shale	2355
shale & lime	2876
lime & shale	3235
shale & lime	3650
shale & sand	3710
shale	3857
lime	4070
lime & shale	4096
shale & lime	4146
lime & shale	4325
shale & lime	4387
lime	4595
lime & shale	4623
shale	4633
shale & lime	4674
shale & lime	4726
lime & shale	4770
Total Depth	

TOPS

Topeka	2950
Elgin	3130
Douglas	3415
Stalnaker	3689
Kansas City	3844
Miss.	4387
Kinderhook	4624
Viola	4726
Simpson	4763

DST 4382-4407 Open 1 hr. Good blow.
 Gas to surface in 50 min. Rec. 120'
 HGCM & spots of oil, 290' GCM wtr.
 w/spots oil. IBHP 1745#. FBHP 1445#.
 FP 75#-390#.

DST 4763-70 Open 1 hr. Good blow.
 Rec. 160' GCM & 3,590' GCSW.
 IBHP 1825#. FBHP 1820#. FP 205#-1695#.