


17-32-7W

Company - AURORA GASOLINE
 Farm - Garber No. 1

SEC. 17 T. 32 R. 7W
 SW SW NE

Total Depth. 4976'
 Comm. 7-20-56 Comp. 8-12-56
 Shot or Treated.
 Contractor. L.C. Smitherman Drlg. Co.
 Issued. 10-27-56

County Harper
 KANSAS



CASING:
 8 5/8" 204' w/200 sx cem.

Elevation. 1418' BB.

Production. Dry

Figures indicate Bottom of Formations

cellar 5
 sand-clay-lime stks 105
 clay-shale w/lime shells 175
 lime-w/shale brks 204
 shale-red bed-lime stks 757
 shale-lime stks 849
 lime-shale 1285
 salt 1300
 lime-shale 1325
 lime w/shale brks 1375
 shale-w/lime stks 1450
 lime-shale 1646
 lime 1813
 lime-shale 2110
 shale-w/lime stks 2216
 lime-shale 3600
 shale 3678
 lime-shale 3775
 shale w/lime stks 3864
 lime 4042
 lime w/shale brks 4107
 lime-shale 4170
 lime 4230
 lime w/shale brks 4275
 lime-shale 4323
 shale-lime cherty 4394
 shale-lime 4401
 chert(Mississippi) 4428
 lime " 4593
 lime-Mississippi-cherty 4624
 lime w/shale 4650
 lime(Miss.) w/shale stks 4681
 lime w/shale 4734
 lime(Viola) 4745
 shale w/lime 4769
 lime-shale brks 4790
 lime-shale w/sand stks 4800
 sand-Simpson 4829
 shale w/sand stks 4851
 sand-Simpson 4872
 sand-shale 4883
 shale-sand strk 4921
 sand-shale 4926
 lime-Arbuckle 4976 RTD
 Total Depth

TOPS: Scout 3273
 Heebner 3391
 B/Oread 3850
 Kansas City 4401
 Mississippi 4722
 Viola 4771
 Simpson Dolomite 4788
 Simpson sand 4932
 Arbuckle