

HARPER L. Co
7-325-7W

MULL DRILLING COMPANY, INC.
#1 Robinson Unit
NW SW SW Section 7-325-7W
Harper County, Kansas

MULL DRILLING CO., INC.
Suite 1625 Wichita Plaza Bldg.
WICHITA 2, KANSAS

Elevation: 1460. KB
Spud: July 5, 1960
Completed: July 16, 1960
Casing: 8-5/8" at 209'/150 sx
Drill Stem Test: #1, 4486-98 (Miss.) oil-cut mud & salt water
Details of test on lithologic log
Electrical Survey: No electrical survey run

<u>Geological Formation</u>	<u>Depth & Datum</u>
Heebner	3346(-1886)
Douglas	3452(-1992)
Stalnaker Sand	3687(-2227)
Kansas City	3922(-2462)
Base Kansas City	4137(-2677)
Mississippian	4483(-3023)

STRUCTURE

Structurally, the #1 Robinson Unit at a -3023 is 32 feet lower on the Mississippian than the Mull #1 Zuercher, one mile south in Section 18. This test was only 16 feet lower than the #1 Zuercher at the base of the Kansas City but had an additional 16 feet of red shale section above the Mississippian.

OIL SHOWS

No oil shows or good zones of porosity were found in the Stalnaker sand or the Kansas City sections.

The top 12 feet of the Mississippian, 4483-95, consisted of fresh milky to partially weathered, mottled, chalky chert. This section had little visible porosity and no staining. The section from 4495-98 had some tan tripolitic chert with small vugular porosity and light staining. This section was tested, and salt water was recovered, condemning this zone for possible production.

Permission was granted to plug and abandon this well.

Robert G. Reinke
ROBERT G. REINKE