

8-32-8W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **DORSET CO.**

SEC. 8 T. 32 R. 8W

FARM **Baker**

NO. **1**

LOC. **C SW SE**

TOTAL DEPTH **4421'**

COUNTY **Harper**


COMM. **10-11-66**

COMP. **10-21-66**

SHOT OR TREATED

CONTRACTOR **Gabbert-Jones, Inc.**

ISSUED **2-4-67**



CASING

20	10	
15	8	5/8 231' w/200 sx cem.
12	6	
13	5 1/2	4384' w/20 sx cem.

ELEVATION **1487' K.B.**

PRODUCTION Temp. **Abnd.**
 (Miss Chert)

FIGURES INDICATE BOTTOM OF FORMATIONS

0	231	RED ROCK
231	630	RED BED AND SHALE
630	1280	SHALE
1280	1400	ANHYDRITE AND SHALE
1400	1830	LIME AND SHALE
1830	1940	LIME
1940	2890	LIME AND SHALE
2890	3010	SHALE AND SHELLS
3010	3285	LIME AND SHALE
3285	3375	SHALE AND SHELLS
3375	3470	LIME
3470	3600	LIME, SHALE AND SAND
3600	3640	LIME AND SHALE
3640	3785	SHALE AND SAND
3785	3886	SHALE AND LIME
3886	4155	LIME
4155	4390	LIME AND SHALE
4390	TO	
	4421	Lime and shale
	CTTD	

RAN 7 JOINTS OF 8-5/8" CASING, SET @ 231' w/200 BAGS CEMENT.

TOPS: SCOUT	SAMPLE
Heebner	3331
Stalnaker	3650
Kansas City	3917
B/Kansas City	4114
Marmaton	4185
Cherokee	4289
Mississippi Chert	4385

RAN 143 JOINTS OF 5 1/2" CASING, SET @ 4384' w/50 BAGS CEMENT.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C SW SE SECTION 8-32S-8W, HARPER COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall

 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 27TH DAY OF OCTOBER, 1966, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED THE USES AND PURPOSES THEREIN SET FORTH.