

6-32-8W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AUFORA GASOLINE CO.
Farm- Hoyt No. 1

SEC. 16 T. 32 R. 8W
NW NW NW

Total Depth. 4773'
Comm. 12-13-57 Comp. 1-4-58
Shot or Treated.
Contractor. Hilton Drlg.
Issued. 7-5-58

County Harper
KANSAS



CASING:
8 5/8" 209' cem w/175 sx.

Elevation. 1447' DF

Production. 21 BOPD

Figures Indicate Bottom of Formations.

red bed & shells	391
red bed, shells & shale	630
shale & shells	1240
shale & lime	1665
lime	1875
lime & shale	3165
lime	3235
lime, sand & shale	3340
lime & shale	3525
shale, lime & shells	3580
sand & shale	3655
lime, sand & shale	3735
lime	4124
lime & shale	4169
lime	4375
Mississippi	4395
chert & lime	4577
lime & shale	4655
shale, lime & chert	4713
lime & chert	4736
lime & shale	4748
sand & shale	4752
sand	4761
sand & shale	4773
Total Depth	

TOPS: SCOUT	
Heebner	3304
Douglas	3354
Kansas City	3872
Base Kansas City	4070
Marmaton	4088
Mississippi	4358
Viola	4686
Simpson	4743
Simpson Sand	4750