

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


17-32-8W

COMPANY **DORSET COMPANY**
 FARM **Robinson** NO. **1**

SEC. 17 T. 32 R. 8W
 LOC. C NE NE

TOTAL DEPTH **4384½'**
 COMM. **7-27-66** COMP. **9-1-66**
 SHOT OR TREATED
 CONTRACTOR **Gabbert Jones**
 ISSUED **10-8-66**

COUNTY **Harper**



CASING
 20 10
 15 8 5/8" 235' cem w/ 200 SX
 12 6
 13 5½" 4361' cem w/ 50 SX

ELEVATION **1456' JB**

PRODUCTION **4,620,000 CFGPD**
 (Miss OH 4360-84½)

FIGURES INDICATE BOTTOM OF FORMATIONS

DEPTH	FORMATION	REMARKS
FROM	To	
0	50	CLAY AND SAND
50	235	RED BED AND SHALE
235	435	SHALE
435	1075	CLAY
1075	1380	SHALE AND SHELLS
1380	1810	SHALE AND LIME
1810	2050	LIME
2050	3455	LIME AND SHALE
3455	3655	SHALE AND SAND
3655	3915	SANDY SHALE AND LIME
3815	3931	SHALE AND LIME
3931	4202	LIME
4202	4340	LIME AND SHALE
4340	4362	LIME
4362	XXXX	
	4384	lime
	Total Depth	

RAN 11 JOINTS OF 8-5/8" CASING, SET 235' W/200 BAGS CEMENT.

RAN 139 JOINTS OF 5½" CASING, SET 4361' W/50 BAGS CEMENT.

TOPS:	SCOUT	LOG
Topeka	3055	3055
Heebner	3291	3291
Douglas		3382
Iata	3577	3577
Stalnaker sand	3614-3747	3614
Base Stalnaker sand		3747
Kansas City	3882	3882
Kansas City Base		4078
Marmaton		4152
Cherokee	4252	4252
Mississippi	4360	4358