


Company - J. M. HUBER CORP. ET AL
 Farm - Fred Fetrow No. 1.

6-32-9W
 SEC. 6 T. 32 R. 9W
 CSE SW

Total Depth. 4910'
 Comm. 10-8-44 Comp. 11-7-44
 Shot or Treated.
 Contractor. J.M.Huber Corp.
 Issued. 12-16-44 Drld w/Rotary

County. Harper
 KANSAS



CASING:
 10 3/4" 700' Cem.

Elevation. _____

Production. Dry

Figures indicate Bottom of Formations.

sand and gravel	27	Sample Tops:	
red bed	60	Wellington	967 Corr.
shells	85	Herrington	1567 Corr.
shells & sand red	295	Winfield	1642 Corr.
red bed & shells	665	Ft.Riley	1742 Corr.
shale & shells	930	Base Fl.Flint	1877 Corr.
salt, shale & shells	1255	Base Wreford	1967 Corr.
lime & shale	2225	Sand	3543
shale & shells	2315		3543-56 shaly & non porous
shale & lime	2575		3556-3605 porous sand, no show
lime, sand & shale	2630	Lansing	3625
shale & lime	2885	Mississippi	4337
lime	2925		4390-4424 porosity, few scattered spots of asphalt. No free oil or odor
Corr. 3004 equals 3066		Base Miss.	4546 Corr.
lime & shale	3280	Viola	4641
shale	3368	Simpson	4713
shale & lime	3474	Arbuckle	4859
shale	3524	Total Depth	4910 - Ran Schlumberger Dry & Abnd.
shale & sand	3554		
sand	3608		
Corr. SLM 3621 equals 3618			
lime & shale	3805	shale sdy	4798
lime	3845	shale & sand	4821
lime hard	3880	lime	4824
lime	3895	sand & shale	4856
cherty lime	3906	conglomerate	4859
lime	4026	lime Arbuckle	4910
lime & chert	4076	Total Depth	
lime & shale	4137		
shale	4198		
shale & lime	4367		
lime soft	4540		
chert	4548		
chert, lime & shale	4560		
shale & lime	4573		
Corr. SLM 4566 equals 4559			
lime & shale	4645		
lime & chert	4669		
lime hard	4740		
shale & sand	4770		