

7-32-9W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MAGNOLIA PETROLEUM COMPANY
Farm- Juanite Stone No. 1

SEC. 7 T. 32 R. 9W
SE SE SW

Total Depth. 4450
Comm. 3-24-56 Comp. 5-23-56
Shot or Treated.
Contractor.
Issued. 8-25-56

County Harper
KANSAS



CASING:

9 5/8" 349' cem w/300 sx.
5 1/2" 4449' cem w/200 sx.

Elevation. 1466

State Pot. P.
Production. 28 BO & 67 BSW in
24 hrs.

Figures indicate Bottom of Formations.

red bed, sand	55
redbed, sandrock, sand	226
sandrock, clay, sand	351
red bed, anhydrite	1141
shale, anhyd.	1501
lime, shale, anhyd.	1977
lime, gypsum, shale	3534
lime, shale, sand	3638
lime, shale, gypsum	3783
lime, shale	4296
lime, shale, chert	4341
Cored #1	4367
Miss. chat, dolomite	4429
lime, chert, dolo. RTD	4450
Total Depth	

Tops:	
Heebner	3393
Douglas sand	3456
Lansing-Kansas City	3609
Mississippi	4340

DST #1 4343-67, open 1 hr, good blow,
gas in 27 min., (TSTM), rec. 90'
O & GCM, 100' HO & GCM, 140' S1. muddy
SW, FP 80 - 190#, BHP 1200#/20 min.