

KANSAS DRILLERS LOG


S. 7 T. 33S R. 1 $\frac{1}{2}$ W

API No. 15 — 191 — 20,546
County Number

Loc. NW NW

County Summer

640 Acres
N



Locate well correctly

Elev.: Gr. 1228'

DF _____ KB _____

Operator
Anadarko Production Company & Diamond-Shamrock Corporation

Address
P. O. Box 351, Liberal, Kansas 67901

Well No. 1 Lease Name Cornelsen "B"

Footage Location
660 feet from (N) line 660 feet from (W) line

Principal Contractor Geologist
Gabbert-Jones, Inc. J. Corry Tinsmon, Consultant

Spud Date Total Depth P.B.T.D.
9-26-75 4315'

Date Completed Oil Purchaser
10-23-75 Permian Corporation

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	286'	Common	300	3% HA-5
Production	7-7/8"	4-1/2"	10.5#	4308'	Pozmix	130	.5% CFR-2 + 1/4# Tuff Fiber/sx

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			4 SPF		4243-45'
Size	Setting depth				
2-3/8"	4250				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production 10-21-75 Producing method (flowing, pumping, gas lift, etc.) Pumping

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	147 bbls.	81 MCF		551 CFPB

Disposition of gas (vented, used on lease or sold) Will be sold Producing interval(s) 4243-45' Simpson

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Anadarko Production Company & Diamond-Shamrock Corporation

Well No.

Lease Name

1

Cornelsen "B"

Oil

S 7 T 33S R 1 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Shale-Shells	0	287		
Lime	287	595		
Shale-Shells	595	1455		
Lime-Shale	1455	2263		
Lime	2263	2525		
Lime-Shale	2525	2735		
Shale-Lime	2735	3111		
Lime-Shale	3111	3175		
Lime	3175	3320		
Lime-Shale	3320	3565		
Shale-Lime	3565	3690		
Lime-Shale	3690	3905		
Shale-Lime	3905	3967		
Lime-Shale	3967	4253		
Lime	4253	4315		
Total Depth		4315		

DST #1 4249-53' Simpson, 15 min PF w/GTS 6 min, open 45 min w/OTS in 40 min, REC 2340' oil, 185' heavy cut and oil cut drilling mud, 123' muddy oil & gas cut salt water. ISIP 1482# (30), PFP 219-243#, FP 298-744#, FSIP 1490# (60), HP 2162-2122#.

USE ADDITIONAL SHEETS, IF NECESSARY TO COMPLETE WELL RECORD.

Date Received

Stanley Shoemaker
Signature
Division Office Supervisor
Title

October 24, 1975
Date