


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WALTERS DRILLING COMPANY
Farm- Attebery No. 2

SEC. 20 T. 33 R. 1W
NW SW SE

Total Depth. 4286'
Comm. 6-16-60 Comp. 7-1-60
Shot or Treated.
Contractor. Walters Drilling Co.
Issued. 9-3-60

County Sumner
KANSAS



CASING:

8 5/8" @ 257' w/150 sks. cem.
4 1/2" @ 4282'6" w/200 sks. cem.

Elevation. 1200' KB

Production. 34 BOPD

Figures Indicate Bottom of Formations.

soil, shale & shells	260
lime & shale	2775
shale	2830
shale & sand	2945
lime & shale	3260
lime & sand	3300
lime	3330
lime & shale	3900
lime	4232
shale & lime	4282
Simpson	4286 RTD
Total Depth	

SCOUT TOPS:

Heebner	2514
Lig	3248
1st Layton	3262
Kansas City	3386
Base Kansas City	3506
Reworked Mississippi	3868
Mississippi Lime	3915
Kinderhook	4215
Chattanooga	4253
Simpson Sand	4282