


XX

State Kansas Field Leslie  
Company Gulf County Meade  
Farm Collingwood No. 2  
Sec. 1 Twp. 33 Range 30

Spot CNW, NW  
Contractor Midwestern Dr/g-



Remarks AD 5800  
Comm. 11-27-56 Comp. 1-23-57  
Elev. DF 2720 GL 2715 KB 2722 TD 5855 PB  
Pay 5695-5715

I.P. <sup>spot</sup> Fla 3180 PD Press. GOR: 967/1  
Casing Record: 13 3/8 ..... 7"  
20" ..... 10 3/4 ..... 5 1/2" 5855/450  
16" ..... 8 5/8 1500/250

Loc	Sample	Log
<del>running 8 5/8</del>	Neab 4389	Neab 4390
<del>DEC 19</del>	Low KC 4539	Low KC 4540
<del>5855/450</del>		Cher 5334
<del>05100</del>		Mor 5661
<del>DEC 19</del>		sd 5690.5-
DST 5689-5720		5720
opt 9 5/8 10"		MISS 5749
opt 1 1/2" FlO Di in 1 1/2"		
est 15 BOPH FP 295-615		
BHP 1788/30 MH 3038		
DST 5757-5855 fail		
ST PA - DST 5788-5810 opt 1 1/2"		
rec 30' m, FP 85-95		
BHP 1410/30		
RTD 5855 new log		
sto @ 5855/450 woc.		

JAN 8 MIC 9 eo 5819 new 61R PF 84/5695-5716  
nan 2" T, FM 20000 sd/20000, FlO load, FlO  
92 BO + 3 BW in 4 hrs 5140 T

JAN 9 ✓  
JAN 16 ✓

JAN 23 <sup>spot</sup> 518 BOPD + 501 MCF  
FCP 1575 SICP 1607  
FTP 575 SITP 1397 GOR 967/1

AMARILLO TOPS

2722 KB

Heebner 4415 (-1603)

Douglas 4425 (-1703)

Lansing 4544 (-1822)

Morrow 5624 (-2902)

"S-2" Sd 5692 (-2970) T 28', per 20', G 518 BOP

Chester 5749 (-3027)

TD 5857 (-3135)