


~~XXX~~ Gas offset

State Kansas Field Stevens EXT
Company Shamrock O & G County Seward
Farm Anthony "B" No. 1
Sec. 1 Twp. 33 Range 31

Spot CNE
Contractor D & M
Remarks cal. Prod. & Unitalprod. F.O.



Comm. 5-12-57 Comp. 6-9-57
Elev. DF 2765. GL 2758. KB TD 5690 PB
Pay D & M

I.P. _____ Press. _____
Casing Record: 13 3/8 _____ 7"
20" _____ 10 3/4 _____ 5 1/2"
16" _____ 8 5/8 2672/900

LOC	Sample	Log
MAY 15 spot φ 1625	Dols 2651	shaw 4261 Hub 4294
MAY 22 95% R WOR		kan KC 4442
MAY 28 φ 3973		Marm 5080
JUN 5 φ 5375		Chen 5249
JUN 12 φ 5565 - 5615 rec 45'		AT 5365
1' marl, 1' ls, 2' marl, 2' sd, 5.0' 1/2 sw		WOR 5578
2' marl, 2' ls, 1' marl, 1' ls, 1' marl,		Chen 5634
3' ls, 28 1/2' sh, 1/2' sh,		
φ 5615-40 rec 25'		
6' sd, 5.0' sh, 19 sh		
DST 5580 - 5640 Plg failed		
rec 530' M FP 210'		
BHP ?		
DST 5578 - 5640 op 4T'		
rec 120' DM, FP 140		
BHP 200/30		
RTD 5690 ran log		

D & M ~~φ~~

AMARILLO TOPS

2766 KB

Heebner 4316 (-1550)

Douglas 4324 (-1558)

Lansing 4441 (-1675)

Morrow 5575 (-2809)

"S-2" Sd 5594 (-2828) T 23', por 0', tst'd M

Miss 5632 (-2866)

TD 5687 (-2921)