

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


5-33-10W

Company- BEARDMORE DRILLING & SUNRAY MID-CONTINENT SEC. 5
Farm- Tucker "B" No. 1

T. 33 R.10W
NE SE SW

Total Depth. 4670'
Comm. 8-30-58 Comp. 9-13-58
Shot or Treated.
Contractor. Beardmore Drilling Co.
Issued. 11-8-58

County Barber
KANSAS



CASING:

8 5/8" @ 232' cem. w/140 sx.

Elevation. 1567' DF - Est.

Production. Dry

Figures indicate Bottom of Formations.

cellar	5
red bed	232
red bed & shale	900
shale & lime	2300
shale w/lime streaks	2445
shale & lime	3758
sand & shale	3350
shale & lime	3980
lime	4099
lime & shale	4142
lime	4265
lime & shale	4295
lime	4400
lime & shale	4570
lime & chert	4665
lime & chert	4670 RTD
Total Depth	

TOPS:

Heebner	3638
Douglas Sand	3758
Lansing	3840
Mississippi	4561

DST #1. 4561-4570 Shut in 20 min.
open 1 hr., shut in 20 min. Rec.
30' mud. IF 15, FF 30, IBHP 1149,
FBHP 331, I. Hydrostatic Pressure
2550, F. Hydrostatic Pressure 2480.
Temp. 112°

DST #2. 4565-4592 Shut in 20 min.
open 1 hr., shut in 20 min., gas in
4 min. not enough to measure. Rec.
60' mud. IBHP 1240, IBHP 1240, FBHP

1120, IF 30, FF 45, I. Hydrostatic
2550, Temp/ 113.

DST #3. 4600-4640 Shut in 20 min.
open 1 hr., shut in 20 min., gas in
9 min., not enough to measure. Rec.
30' mud, 180' slightly oil and gas
cut mud, 60' muddy water, 60' salt
water - total fluid 330'. IBHP 1630
FBHP 1525, IF 45, FF 130, I. Hydro-
static 2540.