

11-33-10W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company: AYLWARD DRILLING COMPANY ET AL
Farm: Garner "A" No. 1

SEC. 11 T. 33 R. 10W
NE NE NE

Total Depth. 4819'

Comm. 12-31-59

Shot or Treated.


Contractor.

Issued. 2-20-60

Comp. 1-17-60

County Barber

KANSAS



CASING:

8 5/8" 205' cem. w/200 sz.

Elevation. 1396 FB

Production. Dry

Figures Indicate Bottom of Formations.

red bed & gyp	170	DST 3674-3743 Open 1 hr. Strong
red rock	500	blow Rec. 1800' salt wtr. IBHP
red rock & shale	600	1500# FBHP 1180#; FP 190#-760#.
shale	1100	
shale & lime streaks	1130	DST 4389-4418 Open 1 hr. Fair blow
shale & shells	1160	to strong blow, dec. to fr. bl.
salt & shale	1300	Rec. 260' OGCM, sl. show wtr.
lime & shale	1455	240' wtry. oil & gas cut mud, 60'
shale & lime	1590	s.w. IBHP 1630# 20 min. FBHP 1580#
lime	1620	30 min., FP 0-180#.
lime & shale	1770	
lime	2000	DST 4779-99 Open 1 hr. Wk. bl.
lime & shale	2255	thruout. Rec. 75' slightly gas cut
shale & lime	3275	mud. 90' mdy. s.w., 90' s.w. IBHP
shale & sand	3469	1720# FBHP 230# FP 25#-80#.
sand	3483	
shale, sand & lime	3590	
shale & sand	3708	
sand	3760	
sand & shale	3830	
lime & shale	3945	
lime w/some shale	4000	
lime-chalky	4067	
lime	4230	
lime & shale	4267	
shale & lime	4375	
lime, shale, chert	4418	
chert	4451	
lime & chat	4505	
chat & chert	4530	
lime & shale	4552	
lime w/shale	4589	
cherty lime & shale	4625	
chalky lime	4665	
lime & shale	4704	
shale & lime	4711	
lime & dolomite	4742	
lime	4792	
sand	4819	
Total Depth		

GEOLOGICAL TOPS:

Begin	3269
Heebner	3418
Toronto	3433
Douglas	3454
Douglas Sand	3469
Stalnaker	3712
Lansing	3814
Kansas City	3948
Base Kansas City	4176
Mormon	4230
Mississippian	4389
Kinderhook	4628
Chattanooga	4672
Viola	4711
Simpson	4792
Simpson Sand	4795