

IMPORTANT
Kans. Geo. Survey request
samples on this well.

15-007-20592

KANSAS DRILLERS LOG

API No. 15 — 007 — 20,592
County Number

Operator
Stelbar Oil Corp., Inc.

Address
950 - 200 West Douglas Wichita, Kansas 67202

Well No. #1 Lease Name
Spicer

Footage Location
660 feet from (N) J&K line 1980 feet from ~~W~~ (W) line

Principal Contractor Sweetman Drilling, Inc. Geologist
Edward B. Donnelly

Spud Date 1-3-78 Total Depth 4646 P.B.T.D.


Date Completed 1-14-78 Oil Purchaser
Koch Oil Co.

S. 29 T. 33 R. 10 ^W

Loc. C NE NW

County Barber

640 Acres
N



Locate well correctly

Elev.: Gr. 1504

DF 1511 KB 1514

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8-5/8	24	368	Common	250	3%cc 2% Gel
Production		4 1/2"		4645		75	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			Perf (MISS) 4610-16		
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1000 MCA	

INITIAL PRODUCTION

Date of first production 3-28-78	Producing method (flowing, pumping, gas lift, etc.) Pumping				
RATE OF PRODUCTION PER 24 HOURS	Oil 40 bbls.	Gas -0- MCF	Water 80 bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
Stelbar Oil Corporation, Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Oil

Well No.

1

Lease Name

Spicer

S 29 T 33S R 10 ~~W~~

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

KB LOG TOPS:

Heebner 3645 - 2131
Stalnaker 3957 - 2443
Lansing 4061 - 2547
Kansas City 4166 - 2652
Miss 4585 - 3071
RTD 4646 - 3132
TD in Miss

DST 1 (Miss) 4572-4600, 30-60-60-120. Rec. 70' Mud, NS. ISIP 637, FP 20-30/30-39, FSIP 734.

DST 2 (Miss) 4600-20, 30-60-60-120. GTS/34", TSTM, Rec 20' VSOSM, 62' SO & GCM, 62' HO & GCM, ISIP 1467, FP 79-79, FSIP 1486

DRILLERS LOG

From

To

Red Bed and shale

0

1594

Shale and lime

1594

4579

Miss.

4579

4645

Total Depth

4645

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Robert W. Patton

Signature

Vice President

Title

September 22, 1978

Date