

Geological Report

American Warrior Inc.
Bedwell, Conner, Dick Trust #1-5
1350' FSL & 335' FEL
Sec. 8 T33S R11W
Barber County, Kansas

James Dilts
Geologist

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 28 2010

CONSERVATION DIVISION
WICHITA, KS

American Warrior, Inc.

General Data

Well Data: American Warrior Inc.
Bedwell, Conner, Dick Trust #1-5
SW-SE-NE-SE
1350' FSL & 335' FEL
Sec. 8 T.33S R. 11 W.
Barber County, Kansas
API # 15-07-23, 321-0000
Lat N 37 11' 59.394078"
Long W 98 31' 57.831854"

Drilling Contractor: Duke Drilling Co., Rig #5

Spud Date: 7/15/2008

Rotary TD Date: 7/21/2008

Elevation: 1438' Ground Level
1450' Kelly Bushing

Casing: Surface 241' 8 5/8" 23# surface casing set at
251' w/ 185 sx 60/40 w/3%cc & 2%gel
Production none (dry hole)

Samples: 10' wet and dry, 3000' to RTD

Drilling Time: 3000' to RTD

Electric Logs: None

Drillstem Tests: Two, Trilobite Testing Inc.

Problems: None

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 28 2010

CONSERVATION DIVISION
WICHITA, KS

Formation Tops

Bedwell, Conner, Dick Trust 1-5

Heebner 3568'-2118
Toronto 3587'-2137
Lansing 3738'-2288
BKC 4252'-2802
Marmaton 4271'-2821
Pawnee 4338'-2888
Ft Scott 4366'-2916
Cherokee 4382'-2932
Mississippi 4399'-2949

Drill Stem Tests

Trilobite Testing Inc.

DST #1 Toronto
Interval (3590' – 3610') Anchor Length 20'
Times: 30-60-30-60
I.F. – Weak Blow IFP 17-23#
I. S. I. - No Blow ISI 1282#
F. F. – Weak Blow FFP 26-32#
F. S. I. – No Blow FSI 1214#

Recovery: 30' MCW %gas %oil 65%w 35%mud

DST #2 Douglas Sand
Interval (3640'-3676') Anchor Length 26'
Times: 30-60-60-90
I.F.-BOB 30 Sec Tapered to 1" IFP 54-185#
I.S.I.-No Blow ISI 1333#
F.F.-Weak Blow BOB 57 Min FFP 199-356#

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 28 2010

CONSERVATION DIVISION
WICHITA, KS

F.S.I.-No Blow

FSI 1324#

Recovery:	45' Drill Mud	%gas	%oil	%w	100%m
	125' MCW			65%w	35%m
	190' MCW			85%w	15%m
	355' SMCW			95%w	5%m

Summary: Due to structural position and DST recovery, the decision was made to plug and abandon the Bedwell, Conner, Dick Trust #1-5.

Respectfully Submitted,

James F Dilts

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 28 2010

CONSERVATION DIVISION
WICHITA, KS