


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

3-33-11W

Company- EULF OIL CORPORATION
Farm- C. D. Williams No. 1

SEC. 3 T. 33 R. 11W
C S/2 N/2
1980' S. N. L. & 2640'
E. W. L.
County Barber
KANSAS

Total Depth. 4590'
Comm. 9-2-56 Comp. 9-20-56
Shot or Treated.
Contractor.
Issued. 11-24-56



Elevation. 1522' DF

Production. 8,200,000 CFGPD

Figures indicate Bottom of Formations.

clay	40
red rock	280
red bed	690
shale	800
shale & lime	1075
shale	1153
shale & shells	1565
lime	1795
shale & lime	3042
lime	3255
shale	3735
sand & shale	3757
shale	3797
lime	4392
lime & shale	4418
lime	4480
Cherty lime	4493
lime	4502
Cherty lime	4590
Total Depth	

SAND RECORD
Mississippi Chert
(4464-4490')

Perf. w/swing jet 4464-90'.
Acidized w/1000 gals. mud acid.
sand fraced w/30,000 gals.
crude 45,000# sand & 1500#
Adomite.

GEOLOGICAL TOPS

Heebner	3612
Douglas sand	3737
Brown lime	3799
Lansing-Kansas City	3803
Mississippi chert	4462
Mississippi lime	4513