

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


9-33-11W

Company. SINCLAIR OIL & GAS CO.
Farm. W. A. Newkirk No. 11

SEC. 9 T. 33 R. 11W
SE NW NW
990' fr NL, 990' fr WL, NW/4

Total Depth. 4525 PBD 4487
Comm. 3-17-55 Comp. 4-5-55
Shot or Treated.
Contractor. Graham-Messman-Rinehart Oil Co.
Issued. 9-17-55

County Barber
KANSAS



Elevation. 1463 DF

Production. 9,200,000 CFGPD

CASING:

10 3/4 @ 240' w/ 200 sx cmt.
5 1/2 @ 4523' w/ 300 sx cmt.

Figures indicate Bottom of Formations.

shale	135
shale & gyp	240
shale	1400
shale & lime	1627
Ft. Riley	1830
shale & lime	3060
lime	3255
lime & shale	3684
coring-Douglas	3704
shale & lime	3720
lime	3850
lime & shale	3878
lime	4208
lime & chert	4236
lime	4370
lime & chert	4399
coring-Mississippi	4450
chert & lime	4458
Mississippi	4525
Total Depth	

Schlumberger TD 4523

TOPS:
Douglas 3645

DST #1: 3678-84; open 1 hr 49 min.
rec. 5,120 MCFG, FP 1155#, BHP 1494#

DST #2: 4402-50, open 2 hrs. Blow,
FP 63#, BHP 1504#

Perf. 12/3642-44, 60/3649-59

Ran Schlumberger & Welex Logs.