

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-33-11W

Company- BARBARA OIL COMPANY
Farm- Page Est. "A" No. 11

SEC. 15 T. 33 R. 11W
NE SE NW

Total Depth. 4592
Comm. 6-23-52 Comp. 8-4-52
Shot or Treated.
Contractor. R. C. Patton
Issued. 10-25-52

County Barber
KANSAS



CASING:
10 3/4" 196' cem w/150 sx
7" 4546' cem w/200 sx

(472 (m))
Elevation. 1171
(471 (m))

Production. 347 bbls & no wtr

Figures Indicate Bottom of Formations.

shale red	200
red shale, shells	840
shale, salt, shells	1455
shale, shells	1540
anhydrite, shale	1780
lime, shale	3704
sand, shale	3800
lime, shale	3946
lime	4048
lime, shale	4234
lime	4264
lime, shale	4288
lime	4310
lime, shale	4500
cored	4592
Total Depth	

Tops:	
Douglas Sand	3704
Lansing-Kansas	3796
Miss.	4485
Top pay	4555
Base pay	4590

IST 4494-4541 open 1 hr
recovered 30' mud & 185' gas.