

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


16-33-11W

Company. SINCIAIR OIL & GAS COMPANY
Farm. W. A. Newkirk No. 9

SEC. 16 T. 33 R. 11W
SE SW SW
330' fr S & 990' f WL of SW/4

Total Depth. 4671; PB 4634
Comm. 1-7-55 Comp. 1-24-55
Shot or Treated.
Contractor. G.M.R. Oil Co.
Issued. 3-19-55

County Barber
KANSAS



CASING:

10 3/4" 246' cem. w/200 sx
5 1/2" 4670' cem. w/250 sx

Elevation. 1451

Production. 251 BO & 88 BW in
20 hrs.

Figures indicate Bottom of Formations.

clay, sand & shale	170
shale & shells	246
shale	1499
shale & lime	1742
Ft. Riley	1935
lime	2080
shale & lime	3142
lime	3210
lime & shale	3944
lime	4052
lime & shale	4091
lime	4510
Mississippi	4548
Coring	4591
Mississippi	4604
lime, shale & chert	4616
lime & shale	4648
Miss. lime	4671
Total depth; PB 4634	
Drillers log corrected to GIM	

Scout Tops:	
Heebner	3594
Douglas sand	3720
Lansing	3806
Mississippi	4480

Mississippian 4480-45961-28-55, 216 holes, 4540' to 4594,
open - Welox jet
1-28-55 Acidized w/500 gal. mud acid
(Dowell) Max Press. 700#, Min 650#,
Inj. Rate 6/10 bbl. per min. Sandoil
frac 10,000 gal. oil, 12000# sand.
Broke formation @ 1500#. Broke to
1250# then to 1150# back to 1200#.
Inj. rate 9 bbl. per min. Flushed w/
25 bbl. oil. Total load and flush 395
bbl.

1-25-55 cement in csg. 4671-4634.

Remarks:
SO & G, 3 cores 4525-4604
Schlumberger log 1-24-55, depth 4671
Welox Jet Serv. 1-29-55, depth 4635