

KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCHAPI No. 15 — 007 — 20,407
County Number

Operator

Kewanee Oil Company

Address

Box 2093 Wichita, Kansas 67201

Well No.

#11

Lease Name

Rhodes Unit Page "C"

Footage Location

2950 feet from (N) line 1640 feet from (E) line

Principal Contractor

Gabbert Jones Drlg. Co.

Geologist

None

Spud Date

April 15, 1976

Total Depth

4570

P.B.T.D.

4554'

Date Completed

May 5, 1976

Oil Purchaser


O.K.C. Corporation

S. 16 T. 33 R. 11 E
W

Loc. 1640' FEL & 2950' FNL

County Barber

640 Acres



Locate well correctly

Elev.: Gr. 1419' C.M.

DF KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	202'	Common	150	3% CaCl
Oil String	7-7/8"	5-1/2"	14# & 15.5#	4569'	50/50 Pozmix	200	3/4% CFR2 10# Gilsonite/ sack-1st 25 sx.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
None			2	Jumbo Jets	4492-4520'
TUBING RECORD					
Size	Setting depth	Packer set at			
2-3/8"	4488'	None			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1000 gal 15% NE Acid.	4492-4520'
Frac w/ 12,000 GO & 6,000 gal KSL Water and 19,500# 20/40 sand.	4492-4520'

INITIAL PRODUCTION

Date of first production May 5, 1976		Producing method (flowing, pumping, gas lift, etc.) Swab			
RATE OF PRODUCTION PER 24 HOURS	Oil 80 bbls.	Gas TLTM MCF	Water 89 bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			-Producing interval (s) 4492-4520'		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
Kewanee Oil Company

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Oil

Well No. 11 Lease Name Rhodes Unit - Page C Lease

S 16 T 33S R 11 E W


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Redbed	0	205		
Redbed-Shale	205	845		
Shale-Shells	845	1535		
Lime	1535	2150		
Lime-Shale	2150	3675		
Sand	3675	3740		
Lime - T.D.	3740	4570		
No Cores. No DST.				
LOG TOPS				
Heebner	3564	-2145		
Douglass Sand	3676	-2257		
Lansing Kansas City	3761	-2342		
Mississippi	4433	-3014		
Page Pay	4492	-3073		
Base of Pay	4534	-3115		
Log T.D.	4572	-3153		
Ran Schlumberger CND, FDC, GR-LL.				
Copies of Elec. Logs mailed to Kansas Geological Survey 4150 Monroe Wichita, Kansas 67209 6-1-76.				
USE ADDITIONAL SHEETS, IF NECESSARY TO COMPLETE WELL RECORD.				

Date Received



C. W. Mosier

Signature

District Manager

Title

June 1, 1976

Date